

PROFESSIONAL SERVICES GUIDE

2008 Edition



Real Estate Development and Planning
FLORIDA INTERNATIONAL UNIVERSITY

University Park – Miami, FL 33199/ Tel: 305.348.4015 Fax: 305.348.4091

PROFESSIONAL SERVICES GUIDE

Table of Contents

ARTICLE 1 Introduction

ARTICLE 2 Understanding the Owner

- 2.1 The Owner
- 2.2 The Chancellor's Authority
- 2.3 The University President's Authority
- 2.4 Professional Services Evaluations

ARTICLE 3 Technical Applications

- 3.1 Communications, Meetings, and Minutes
- 3.2 Project Schedule
- 3.3 Status Reports
- 3.4 Site Information
- 3.5 Surveys
- 3.6 Geotechnical Services
- 3.7 Materials and Equipment
- 3.8 Protective Construction and/or Fallout Shelter in Public Buildings
- 3.9 Federal or Local Government Participation
- 3.10 Available Consulting Services
- 3.11 Utility Information and Service Requirements
- 3.12 Wage Rates
- 3.13 Code Compliance and Permits
- 3.14 Cost Estimates and Area Measurements
- 3.15 Building Program
- 3.16 Owner's Minority Business Enterprise (MBE) Utilization Program
- 3.17 Building Telecommunications and Cable Television Systems
- 3.18 Fume Hood Exhaust, 100% Outside Air Systems and Other
- 3.19 Specialized HVAC Systems

ARTICLE 4 Design and Construction Documents

- 4.1 Standards for Construction Documents
- 4.2 Errors and Omissions
- 4.3 Conceptual Schematic Design
- 4.4 Advanced Schematic Design
- 4.5 Design Development
- 4.6 Construction Documents

ARTICLE 5 Bidding and Contract Award

- 5.1 General Contractor Projects
- 5.2 Construction Manager Projects

ARTICLE 6 Construction Administrations

- 6.1 General
- 6.2 Construction Conferences
- 6.3 Contractor's Required Submittals
- 6.4 Clarification of Drawings and Specifications
- 6.5 Applications for Payment
- 6.6 Change Orders and Construction Change Directives
- 6.7 Claims
- 6.8 Beneficial Occupancy
- 6.9 Substantial Completion
- 6.10 Final Completion
- 6.11 Post-Occupancy Inspection

ARTICLE 7 Administrative Applications

- 7.1 Additional Service Authorizations
- 7.2 Reimbursable Expenses
- 7.3 Invoicing

PROFESSIONAL SERVICES GUIDE

TABLE OF EXHIBITS

EXHIBIT 1	Professional Services Evaluation Form
EXHIBIT 2	Planning and Design Status Report
EXHIBIT 3	Construction Phase Status Report
EXHIBIT 4	Land Survey – Request for Proposal
EXHIBIT 5	Fire Marshal Document Review Procedure
EXHIBIT 6	Architect/Engineer’s Estimate Summary & Budget Comparison
EXHIBIT 6A	Building Classification for Energy Consumption
EXHIBIT 7	Title Block Information
EXHIBIT 8	Title Sheets, Pages and Bindings
EXHIBIT 9	SUS Energy Life Cycle Cost Analysis Summary Form
EXHIBIT 10	Document Submittal and Review Checklist
EXHIBIT 11	Document Distribution Record
EXHIBIT 12	Bid Tabulation Form
EXHIBIT 13	Construction Contract Fact Sheet
EXHIBIT 14	SUS Standard Invoice Form
EXHIBIT 15	Sample Completed Invoice Form
EXHIBIT 16	Travel Reimbursement Form
EXHIBIT 17	Contract Documents Cost Recap Sheet

PROFESSIONAL SERVICES GUIDE

ARTICLE 1

INTRODUCTION

1.1 The December, 1998 edition of the State University System Professional Services Guide supersedes all previous editions. Its purpose is to assist the Architect/Engineer in providing services to the State University System of Florida. The Guide does not modify the scope of work or the contractual obligations of the Agreement between Owner and Architect/Engineer (the Agreement). The Guide does not repeat the requirements of the Agreement, the Project Manual, or the Owner/Contractor Agreement; rather, it explains how to fulfill the requirements of these documents.

1.2 The Guide will enable the Architect/Engineer to better understand the Owner and the authority delegated to those entities and persons with whom the Architect/Engineer will routinely work. The most frequently asked questions concerning the interactions between the Owner and the Architect/Engineer are addressed.

1.3 On smaller projects, particularly those designed by a Campus Service Architect/ Engineer, some of the procedures (e.g. phases required, etc.) may differ slightly. The university will advise the Architect/Engineer of the differences.

ARTICLE 2

UNDERSTANDING THE OWNER

2.1 The Owner

2.1.1 The Owner is the university on behalf of the Florida Board of Regents (Board). This corporate board governs the State University System of Florida which consists of the ten universities and the Board's central office staff. The Board is housed within the administrative structure of the Florida Department of Education as the Division of Universities. The Board has statutory authority to administer the construction program.

2.1.2 The university president is granted authority by statute to execute design and construction contracts and is granted authority by administrative rule to administer the construction program. The Board has retained approval authority on some items relating to the construction program, as described below.

2.1.3 Funds for construction are appropriated, or authorized, by the Florida Legislature. The Board is accountable to the legislature for their proper expenditure. In discharging this accountability, the Board delegates certain authority for the construction program to the university president, and retains certain authority for the Chancellor. The construction responsibility of the university president is administered by the university facilities planning office, or in some cases, the physical plant office.

PROFFESIONAL SERVICES GUIDE

Florida International University

2.2 The Chancellor's Authority (may be the Chancellor or designee)

2.2.1 Approve the building program and any amendments. The building program is the planning document from which the legislative budget request is generated and from which the Architect/Engineer will develop plans and specifications. A deviation from the approved building program requires a program amendment which has been approved by the Board Office of Facilities Planning.

2.2.2 Approve the project budget and any amendments.

2.2.3 Establish the Board's Cost Containment Guidelines.

2.3 The University President's Authority (may be the President or designee)

2.3.1 Prepare the building program and submit it to the Chancellor for approval and subsequent submission to the Governor's Office of Planning and Budgeting. Any change to the approved building program must also be submitted for approval.

2.3.2 Appoint the Architect/Engineer or other design professionals. The selection process is conducted under Section 287.055, Florida Statutes, and Rule 6C-14.005, Florida Administrative Code.

2.3.3 Determine the method for acquiring a construction project and advertising and awarding contracts for construction management, design-build, or competitive bid of construction work

2.3.4 Appoint the Construction Manager as provided under Rule 6C-14.0055; or award the general construction contract as provided under Rules 6C-14.018 and 6C-14.021, F.A.C.

2.3.5 Review and approve design documents at each phase of development. Act as the Owner's Project Manager and make decisions with respect to building plans, provided these decisions are consistent with the approved building program, the approved campus master plan, the approved budget, and the Board's Cost Containment Guidelines.

2.3.6 Approve each request for Additional Services to be provided by the Architect/ Engineer.

2.3.7 Review and approve invoices for professional services and contractors' pay requests.

2.3.8 Approve change orders and construction change directives during the construction phase.

2.4 Professional Services Evaluations

2.4.1 The Architect/Engineer will be evaluated by the university twice annually while under contract (a sample evaluation form is included as Exhibit 1).

2.4.2 The evaluations will be kept on file in the BOR Office of Facilities Planning for three years; and will serve as the basis for the Past Performance scores in selections for future projects.

ARTICLE 3

TECHNICAL APPLICATIONS

3.1 Communications, Meetings and Minutes

3.1.1 The Agreement is between the Architect/Engineer and the Florida Board of Regents; however, the university facilities planning office, when so designated by the University President, shall serve as the Owner's Project Manager (hereinafter referred to as the University Project Manager) and the channel for all official communications with the Architect/Engineer in administering a project. The university facilities planning office will act within the limits of its delegated authority.

3.1.2 Prior to or immediately following the issuance of the Notice to Proceed, the University Project Manager will provide a list of those persons who shall be routinely copied on all written communications (Owner's Distribution List) to the Architect/Engineer. All written communications must include the state project number.

3.1.3 The Architect/Engineer, in consultation with the University Project Manager, shall schedule all necessary conferences and meetings with persons involved in the project to obtain project information and to maintain project progress.

3.1.4 The Architect/Engineer shall record the minutes of all scheduled meetings, presentations, developments, and conferences, and furnish copies of these minutes within fifteen (15) calendar days to all attendees and to the persons identified on the Owner's Distribution List. The Architect/Engineer shall list the names of those persons receiving the distribution of the minutes as an attachment to the minutes. The minutes shall be concluded with the following statement: *It is responsibility of all meeting attendees to bring all omissions, corrections, and/or errors in these minutes to the attention of the undersigned and the university within 14 calendar days.*

3.1.5 All conferences, telephone conversations, consultations and meetings which resolve or establish a question of scope, a design element or other consideration of project development, shall be confirmed in writing by the Architect/Engineer with copies to all parties to the communication and to the Owner's Distribution List.

3.1.6 The Architect/Engineer shall provide written response to all Owners' written document review comments within 10 calendar days.

3.2 Project Schedule

3.2.1 The schedule of services is part of the contract negotiation and is included in the Agreement. The Notice to Proceed is effective upon receipt of the Notice to Proceed or on such other date as may be specifically referenced in the Notice to Proceed. Within 14 calendar days after the effective date of the Notice to Proceed, the Architect/Engineer shall deliver to the University Project Manager a project schedule identifying the specific dates for all phases applicable to the project. The project schedule will firmly establish the date sequence for planning, design, bid, construction, and occupancy of the facility to be constructed. The project schedule shall define the project's critical path and indicate all milestones necessary for the completion of each phase, and identify intervals for the Owner's review and approval.

PROFFESIONAL SERVICES GUIDE

Florida International University

The project schedule shall also identify the licenses, permits and approvals anticipated to be required by governmental and regulatory agencies, and the date/time sequence involved in each application, including all Owner-filed applications and pre-clearances for contractor-filed applications.

3.2.2 The Architect/Engineer shall maintain the project schedule throughout the life of the project, revising it at the completion of every phase as necessary to maintain the approved time parameters, and to inform the University Project Manager of changes in the actual or anticipated progress of the project.

3.3 Status Reports

3.3.1 The Architect/Engineer is required to keep the Owner informed concerning the progress of the project. The Architect/Engineer shall submit to the University Project Manager by the fifth day of each month, a report describing in detail the progress that has been made as of the end of the prior month. This report shall commence at the end of the month following the Notice to Proceed and continue through Final Completion. The report shall discuss progress made and any critical items needing attention or any areas that might cause future delay. The format for the planning and design phase is shown as Exhibit 2 and for the construction phase is shown as Exhibit 3.

3.4 Site Information

3.4.1 The Architect/Engineer shall visit and inspect the site and location of the work, including the general surrounding area, as often as required to be fully acquainted with all pertinent local conditions affecting the development of the project.

3.4.2 The University Project Manager will provide information relative to the site. The Architect/Engineer may request the University Project Manager to provide additional information, if deemed necessary, and the University Project Manager shall furnish the additional information or shall direct the Architect/Engineer to obtain it at the Owner's expense. The Architect/Engineer shall evaluate and verify all information provided by the University Project Manager.

3.4.3 When a project includes extensive renovations, restoration or remodeling of an existing building, the University Project Manager shall provide the Architect/Engineer with record drawings of the facility. The Architect/Engineer shall verify the accuracy of the record drawings, as necessary, to develop accurate construction documents. If, however, extensive verification is required due to inaccuracy of the record drawings, or if the Architect/Engineer is required to develop measured drawings, an Additional Service Authorization will be issued as provided by Paragraph 7.1. If authorized, the Architect/Engineer shall investigate existing conditions, both in the open and those that are hidden, in addition to preparing the required measured drawings. The Architect/Engineer shall take all necessary action to expose the existing construction in order to determine its exact condition, including removing all coverings, plant growth, etc. When the exposure of existing surface or subsurface construction is considered necessary, the Architect/Engineer shall arrange with the University Project Manager for the work to be done.

3.4.3.1 The University Project Manager will provide the Architect/Engineer with existing information regarding asbestos and lead-based paint surveys and Operations and Maintenance Plan activities.

PROFFESIONAL SERVICES GUIDE

Florida International University

3.4.4 When the investigation of a site is provided under the Agreement, the Architect/Engineer shall obtain all plan reviews and approvals for the licenses and permits that is a necessary precedent to construction or bidding for that work. The Architect/Engineer shall comply with all applicable laws, codes, and regulations in connection with the work and provide for proper safety precautions to protect the public and public property. The cost of any permits required and the investigation are reimbursable expenses and must be authorized by the university as an Additional Service prior to their occurrence.

3.4.5 The University Project Manager will provide the Architect/Engineer with ADA accessibility survey information.

3.5 Surveys

3.5.1 The Architect/Engineer shall consult with the University Project Manager to determine if a survey of the site is available. If one is not available, the Architect/Engineer shall determine the scope of surveying needs. The format for recording the surveying needs is shown in Exhibit 4.

3.5.2 When so requested by the University Project Manager to obtain a survey, the Architect/Engineer shall select a qualified surveyor and provide a proposal to the University Project Manager. The university will issue an Additional Service Authorization.

Payment for the cost of the survey will be made in accordance with Paragraph 7.3.

3.5.3 The survey shall contain the following:

3.5.3.1 Land (Boundary) Survey.

- .1 All headings and distances of property lines of all parcels which comprise the site.
- .2 The dimensions, locations and ownership of buildings, structures, easements, rights-of-way, setbacks, encroachments on the site including block or street numbers, and the presence of any developed mineral rights to which the site is subject.
- .3 Details of all party walls, walls, fences and foundations on the site and adjacent to, or within five feet of, the property lines.
- .4 Where no monument exists, suitable permanent monuments shall be set at property comers and at other appropriate locations.
- .5 Area of site in acres (to .001 acre) and in square feet if less than one acre.
- .6 Zoning of property and adjacent properties.
- .7 Certification on the survey drawings by the city engineer or other qualified official that the officially established or anticipated widening' or changes to street lines, grades or curbs, sidewalks, services, and sewers are correctly shown.
- .8 The full legal description of the parcel shown and an indication if the parcel is part of a parent tract.
- .9 Certification, seal, and signature of a Land Surveyor registered in the State of Florida.

PROFFESIONAL SERVICES GUIDE

Florida International University

(NOTE: Any discrepancies between the land (boundary) survey and the recorded legal description shall be reconciled and explained.)

3.5.3.2 Topographic Survey

- .1 All of the items listed under Clause 3.5.3.1, Land (Boundary) Survey above.
- .2 The position, dimension, elevation and contours of all cellars, excavations, wells, backfilled areas and similar openings and the elevation of any water therein.
- .3 Existing trees, their identities in English and botanical terms, trunk sizes and approximate foliage areas. Generally, only trees six inches or larger in trunk diameter shall be considered, unless they are previously landscaped trees or specimen trees.
- .4 Existing major shrubs, undergrowth and ground cover areas.
- .5 Detailed information required establishing curb and building lines, street, alley, sidewalk and curb grades and lines at or adjacent to the site and a description of the materials of which they are constructed.
- .6 Floor elevations of all floors of existing buildings to be renovated or to which additions will be made.
- .7 All known utility services, including pipe sizes, pressures and electrical characteristics. The location, invert elevations and direction of flow of all piping, mains, sewers, poles, wires, hydrants, catch basins and manholes upon, over, or under the site, or adjacent to the site within the approved scope of the survey, including but not limited to buried tanks and septic fields serving, or on the property, and including the name of the operating authority of each utility.
- .8 Flood plain, flood levels of streams or adjacent bodies of water and an analysis of the site for potential flooding, including the extent of watershed on the property. A statement of the probability of water overrunning the site and the indication of the One Hundred (100) Year flood elevation and contour.
- .9 Location of test borings and soil borings where ascertainable.
- .10 The official data upon which elevations are based and the bench mark established on or adjacent to the site shall be clearly indicated. *Only one such data point or bench mark shall be used on anyone site for establishing the grades for a project.*
- .11 Contours and elevations on a grid system of not more than fifty feet intervals shall indicate changes of slope over that portion of the site to be developed. The interval for contours shall be tailored to the site under consideration.
- .12 The contemplated date and description of any known or proposed improvements to the approaches or utilities on or adjacent to the site.

3.5.4 The survey drawings are often included in the Contract Documents. If the survey drawing is complex, it may be included in the Contract Documents as is, followed by a simple site plan showing the buildings and proposed project work.

PROFFESIONAL SERVICES GUIDE

Florida International University

3.6 Geotechnical Services

3.6.1 The Architect/Engineer shall advise the University Project Manager when an investigation and testing of geotechnical conditions are necessary and shall define the scope of work required. The format to be used for defining geotechnical services requirements is the current edition of AIA Document G602, Geotechnical Services Agreement.

3.6.2 Upon approval by the University Project Manager to obtain subsurface investigation and testing services, the Architect/Engineer shall select a qualified firm and forward a proposal to the University Project Manager. The university will issue an Additional Service Authorization. Payment for the cost of geotechnical services is made in accordance with Paragraph 7.3.

3.6.3 If additional subsurface investigation and testing is required when the results of the initial exploration are received, the Architect/Engineer shall submit to the University Project Manager an estimate from the testing firm for additional investigations to be performed. The Architect/Engineer shall not proceed with the additional investigation until the revised Additional Services Authorization is received from the university.

3.6.4 The Architect/Engineer shall provide grade, foundation, and structural design solutions based on the geotechnical engineer's analysis and recommendation, and shall submit such analyses and reports to the University Project Manager.

3.7 Materials and Equipment

3.7.1 Cost Containment Guidelines for design and construction are issued by the Board Office of Facilities Planning. These standards relate primarily to the building exterior wall system, roofing system, and HVAC systems. These minimum standards must be addressed. The University Project Manager will furnish the Architect/Engineer with the Cost Containment Guidelines and the university supplement to the Cost Containment Guidelines.

3.7.2 The Architect/Engineer will select materials and equipment which are appropriate for the exposure to which they will be subjected, giving consideration to obtaining an extended useful life with low operating and maintenance cost. Evaluation of operating and maintenance costs shall be a part of any initial materials and equipment decision. Products which have not achieved a minimum five-year period of successful use in the construction market shall not be used, unless approved in writing by the Board Office of Facilities Planning. Roofing products require a longer proven history; the Architect/Engineer will discuss these requirements with the University Project Manager.

3.7.3 The Architect/Engineer shall prepare drawings and specifications so that the Bidder is permitted a choice of competitive materials or methods which are equally satisfactory for the intended purpose and comparable in cost. The Architect/Engineer shall not use exclusive requirements when specifying equipment and materials on drawings and specifications. The drawings and specifications must permit competition consistent with the work involved. When it is necessary to designate equipment and materials by product name, at least two equivalent products shall be named and the opportunity provided for other products to be submitted for approval in order to qualify before the bid date.

3.7.4 If a proprietary specification for materials or equipment is required, the Architect/Engineer shall secure approval of the University Project Manager prior to its use in the drawings and specifications. *The use of a proprietary specification must be sufficiently justified and the request and approval must be in writing, as required by Section 255.04, F.S.*

PROFFESIONAL SERVICES GUIDE

Florida International University

3.8 Protective Construction *and/or* Fallout Shelter in Public Buildings

3.8.1 Section 255.042, Florida Statutes, provides that protective construction *and/or* fallout shelters should be considered when constructing public buildings. The degree of compliance will depend on factors which vary with the type, size, location, and cost of the individual structure or facility. Unless specifically instructed otherwise, the Architect/Engineer will consider such protective construction in the planning and shall provide an evaluation of its cost.

3.8.2 The investigation and design for protective construction is considered a Basic Service under the Agreement. If in-house expertise to accomplish this evaluation is not available, the Architect/Engineer shall contact the Department of Community Affairs, Division of Emergency Management, Bureau of Operations, for assistance.

3.9 Federal or Local Government Participation

3.9.1 Whenever a project involves funding participation by federal or local governmental agencies, the Architect/Engineer shall ascertain the requirements of such participation and comply fully with these requirements in the Contract Documents. The Architect/Engineer may be assisted in this task by the University Project Manager. Where grants constitute any part of the project funding, the Architect/Engineer shall ascertain which conditions of "the grant funds must be addressed in the Contract Documents.

3.10 Available Consulting Services

3.10.1 Many state agencies have qualified specialists available for consultation and/or coordination, and they should be contacted when the items within their jurisdiction are pertinent to the development of the project. The Architect/ Engineer shall review the project with the University Project Manager to determine which agencies should be consulted.

3.11 Utility Information and Service Requirements

3.11.1 The Architect/Engineer shall assure that all utilities and services required for the successful functioning of the facility have been provided to the site and will be in full service upon completion of the facility. Some of the university storm water systems have been designed as pressure gradient systems capable of creating back pressures on lateral tie-ins. The nature of the system shall be identified by the Architect/Engineer and the tie-in from the building must be compatible with it.

3.12 Wage Rates

3.12.1 State wage rates are not required. Wage rates are only applicable to federally funded projects. The Architect/Engineer shall obtain rates for federally funded projects from the regional office of the granting agency.

3.13 Code Compliance and Permits

3.13.1 The Architect/Engineer shall ensure that the design and Contract Documents comply with all applicable codes, regulations, and orders. The Architect/Engineer shall submit a list of codes to which the project is subject to the university with the Conceptual Schematic Design submittal. All reference to codes herein shall mean the latest editions adopted through legislation for use in state owned leased buildings.

PROFFESIONAL SERVICES GUIDE

Florida International University

3.13.2 The Architect/Engineer shall use the following codes (where code requirements conflict, the university will resolve any disputes of code application):

3.13.2.1 Building Codes: In all counties, the Standard Building Code, excluding fire prevention, including the Standard Plumbing Code, Standard Gas Code and Standard Mechanical Code. Regarding lateral loads, if local codes have more stringent requirements, local codes shall govern.

3.13.2.2 Fire and Life Safety:

- .1 National Fire Protective Association codes and regulations, including the Life Safety Code.
- .2 Fire Protection Rules and Regulations of the State Fire Marshal.

3.13.2.3 Electrical and Plumbing Codes:

- .1 National Electric Code, NFPA 70.
- .2 Florida Electrical Code, Sections 553.15 through 553.23, Florida Statutes.
- .3 State Plumbing Code, Section 553.06, Florida Statutes.
- .4 In those locations where electrical and plumbing utilities are provided by a local governmental agency, the local plumbing and electrical codes.

3.14.2.4 Other Requirements:

3.13.2.4.1 Rules of the Department of Business and Professional Regulation, Division of Hotels and Restaurants, Bureau of Elevator Inspection.

3.13.2.4.2 Rules of the Agency for Health Care Administration. There is a fee for the review required by Chapter 59A-3.

3.13.2.4.3 Accessibility.

- .1 Florida Accessibility Code for Building Construction, 1994, Department of Community Affairs, Florida Board of Codes and Standards.
- .2 Florida ADA Implementation Act.
- .3 Americans with Disabilities Act of 1990 with current revisions.
- .4 HUD Fair Housing Act for Multi-Family Residential Construction.
- .5 Florida Public Service Commission - installation and replacement of public Telephones.
- .6 State Traffic Operations Engineer - FOOT - government parking facilities

PROFFESIONAL SERVICES GUIDE

Florida International University

- .7 Agency for Health Care Administration - hospital and health care facilities
- 3.13.2.4.4 Life Cycle Analyses (addressed in Section 4.4.1.9 herein).
- 3.13.2.4.5 Department of Education space standards contained in the Size of Space and Occupant Design Criteria Table, State Requirements for Educational Facilities.
- 3.13.2.4.6 Asbestos and Lead-Based Paint Surveys, Operations & Maintenance, and Abatement:
 - .1 Rules of the Florida Department of Labor and Employment Security
 - .2 Requirements of Sections 255.551-565 and Chapter 469, Florida Statutes
 - .3 Rules of the Florida Department of Environmental Protection
 - .4 Regulations of OSHA and the Environmental Protection Agency
 - .5 Licensing regulations of Asbestos Consultants, the Florida Department of Business and Professional Regulation
 - .6 Lead-based paint minimum abatement standards of the Department of Housing and Urban Development and current state of the art procedures to protect university personnel, students and visitors
 - .7 All asbestos abatement contractors are to be pre-qualified under the SUS Owner, Provided Insurance Program
- 3.13.2.4.7 Rules of the Department of Environmental Protection.
- 3.13.2.4.8 Rules of the area Water Management Districts.
- 3.13.2.4.9 Mechanical, Heating, Ventilating and Air Conditioning (HVAC) systems and equipment design and installation shall comply with American Society of Heating, Refrigerating and Air Conditioning Engineers, Inc. (ASH RAE) Handbooks; American Conference of Governmental Industrial Hygienists Ventilation Manual; American Society of Mechanical Engineers' Unfired Pressure Vessel Code; and American Standards Institute (ANSI) standards.
- 3.13.2.4.10 The Trench Safety Act as described in Sections 553.60-64, F.S.
- 3.13.2.4.11 Requirements for threshold buildings as described in Section 553.79, F.S.
- 3.13.2.4.12 Any codes applicable to the project which are enacted after the publication of this Guide.

3.13.3 The State Fire Marshal has statutory responsibility for review of all plans. Plans for review by the State Fire Marshal shall be submitted through the University Facilities Planning Office. Liaison with the State Fire Marshal's staff will be provided by the University Facilities Planning Office. The current State Fire Marshal document review procedure is included as Exhibit 5. If this procedure is updated prior to the next edition of this Guide, the updated procedures shall be adhered to.

PROFFESIONAL SERVICES GUIDE

Florida International University

3.13.4 The Architect/Engineer shall confer with the University Project Manager to determine those permits to which the project is subject. The Architect/Engineer shall ensure that the design and contract documents are capable of obtaining all required approvals and permits. Required permits include those necessary for the design as well as those needed by the contractor for actual construction work. The Architect/Engineer shall determine the requirements of each permit, confer with the appropriate officials, submit all required information to obtain approval, and submit the Contract Documents for approval by the applicable agencies.

3.13.5 Sources of the required permits and approvals are:

.1 City and County. Special provisions for campus planning and concurrency, which supersede the requirements of Part II of Chapter 163, F.S., were established by the legislature with the creation of Section 240.155, F.S., to ensure that universities are developed or expanded in a manner consistent with principles of good growth management. These provisions allow for the establishment of key development policies and standards in the planning stage. After review by local, regional and state agencies, these policies and standards serve as the basis for a limited or expedited development review and approval process. Until the campus development agreement is executed, the Architect/Engineer shall identify any reviews and permits required for concurrency and consistency with the local comprehensive plan, including the cost, professional fees, and schedule. Unless specifically included in the basic services, the Architect/Engineer shall not initiate the local review/permitting process for a project without an Additional Service Authorization or other written authorization from the university. Pursuant to Section 240.293, F.S., the Owner is not obligated to obtain or to pay for building permits from city or county agencies; however, projects where a local governmental entity is providing utility services may be subject to permits and inspections for plumbing and electrical installations by the local entity.

.2 Department of Business and Professional Regulation, Division of Hotel and Restaurants, Bureau of Elevator Inspection. The contract documents must show the complete elevator installation including all details, hoistways, mechanical rooms, and other areas affecting the installation, and access to the elevator installation. The necessary structural and mechanical data describing the complete installation shall be included. The elevator subcontractor shall be required to submit documents to the Bureau of Elevator Inspection for approval prior to construction. The Architect/Engineer shall incorporate any required changes into the construction documents.

.3 Agency for Health Care Administration (AHCA), Plans and Construction Office. All additions or modifications to hospital facilities are subject to the rules and standards promulgated by AHCA. The Architect/Engineer shall contact AHCA to determine their requirements.

.4 Department of Environmental Protection (DEP), area District Branch. All projects are subject to the environmental requirements of the Department of Environmental Regulation. The Architect/Engineer shall contact the area DEP office to determine the environmental requirements for the project.

.5 Water Management District, area District Office. All projects are subject to the regulations relating to water management through the area Water Management Districts. The State University System is required to pay the permit fee of the area Water Management District. The Architect/Engineer shall contact the area Water Management District to determine the water management requirements for the project.

PROFFESIONAL SERVICES GUIDE

Florida International University

3.14 Cost Estimates and Area Measurements

3.14.1 The Architect/Engineer shall ensure that an accurate cost estimate is provided with each design submission. This cost estimate shall also include a comparison to the approved budget. The approved budget is the amount included in the Architect/Engineer agreement. The Architect/Engineer shall not design a project exceeding the approved budget without written notice from the Board Office of Facilities Planning or the Board Office of Budgets that the budget has been increased. Unless otherwise indicated, space measurements shall be made in accordance with the State Requirements for Educational Facilities (SREF), maintained by the Department of Education.

3.14.2 Space measurements for the purpose of operating budget requests are slightly different from the definition in SREF. In addition to square footage information provided based on SREF definitions, the Architect/Engineer shall also provide the university with total square footages based on the following criteria:

3.14.2.1 Building Gross Square Feet: Determine the total building gross square feet by adding the sum of the floor areas of the building included within the outside faces of exterior walls for all stories, or areas that have floor surfaces. Gross area should be computed by measuring from the outside face of exterior walls, disregarding cornices, pilasters, buttresses, etc., which extend beyond the wall face. Gross area should include basements (except unexcavated portions), attics, garages, enclosed porches, penthouses, mechanical equipment floors, lobbies, mezzanines, all balconies (inside or outside) utilized for operational functions, and corridors, provided they are within the outside face lines of the building. Roofed loading or shipping platforms should be included, whether within or outside the exterior face lines of the building. Stairways, elevator shafts, mechanical service shafts, and ducts are to be counted as gross area on each floor through which the shaft passes. Exclude open courts and light wells, portions of upper floors eliminated by rooms or lobbies that rise above single floor ceiling height, and non-enclosed covered walkways.

3.14.2.2 Net Assignable Square Feet: Determine the sum of room areas excluding non-assignable areas. *Room area* is defined as the net area of the room in square feet, measured between the inside surfaces of the walls and partitions. *Non-assignable areas* include interior circulation space (including stairs), custodial areas, mechanical areas, structural areas, public rest rooms, exterior circulation space (including stairs), elevators, and telephone/data communication equipment areas.

3.14.2.3 Covered Walkway Gross Square Feet. Measure floor area, excluding any areas which were included in the calculation for Building Gross Square Feet in Clause 3.14.2.1 above.

3.14.3 The format for the Architect/Engineer's Estimate Summary and Budget Comparison is shown in Exhibit 6.

3.15 Building Program

3.15.1 The Architect/Engineer's execution of the Agreement implies acceptance of the building program and the design shall incorporate all its requirements. The Architect/Engineer may obtain amplification and details concerning the building program requirements from the University Project Manager. The Architect/Engineer shall confirm such details and amplifications by memorandum to the University Project Manager with a copy to the BOR Office of Facilities Planning. The Architect/Engineer shall not perform professional services which vary from the approved building program without the written prior approval of the BOR Office of Facilities Planning.

PROFFESIONAL SERVICES GUIDE

Florida International University

3.15.2 Any modification to the building program recommended by the University Project Manager and/or the Architect/Engineer shall be submitted to the BOT Office of Facilities Planning for approval. The request for a building program amendment shall include a complete description of the proposed change and a narrative justification, including its impact on the project's budget and schedule. If the proposed program amendment will involve professional services not covered under the Agreement, an estimate of the cost of such services prepared by the Architect/Engineer shall be included in the amendment request. If the building program amendment is approved, the university will issue a directive to the Architect/Engineer instructing the change(s) be made and authorizing the additional professional services. In the absence of an approved program amendment, the original program requirements shall prevail.

3.16 Owner's Minority Business Enterprise (MBE) Utilization Program

3.16.1 The Architect/Engineer is advised that the Owner's MBE goals for construction require the expenditure of 21% of each annual appropriation with minority business enterprises. Construction managers may be required to include MBE firms in 30% of their overall contract amount, and general contractors are given preference for the amount of MBE participation they demonstrate on the bid form. Throughout design, the availability of minority subcontractors should be a factor in the Architect/Engineer's decisions regarding the selection of types of construction, systems and materials.

3.17 Building Telecommunications and Cable Television Systems

3.17.1 Each university in the State University System has adopted telecommunications standards. Telecommunications typically includes telephone and computer data systems combined in one set of wiring.

3.17.2 Basic Services include:

3.17.2.1 Building telecommunications wiring and conduit from the main building telecommunications room to all rooms and spaces within the building, and wall boxes and termination devices in those rooms and spaces.' Basic Services also include telecommunications conduit from the main building telecommunications room to the nearest telecommunications manhole or building as the university directs. This telecommunications scope shall be included in the Project's Base Bid scope.

3.17.2.2 Cable television systems where required, including wiring and conduit from a designated building location to all rooms and spaces within the building requiring cable television, and wall boxes and termination devices in those rooms and spaces.

3.17.3 Additional Services will be considered only when fiber optics is to be included in the Architect/Engineer's scope, and a special consultant is needed.

3.18 Fume Hood Exhaust, 100% Outside Air Systems and Other Specialized HVAC Systems

3.18.1 Introduction. Building spaces with fume hoods and animal holding facilities typically are prohibited by Code and good practice from recirculation of air conditioning air: 100% outside air is required. Clean room "Class" per ASHRAE must be determined and documented. Since 100% outside air systems and other special systems are expensive to build, operate and maintain, and since the size and complexity of

PROFESSIONAL SERVICES GUIDE

Florida International University

the systems create ample opportunity for design, contract, construction, initial start-up and noise problems, it is critical that the detailed design basis and costs be established and documented in early design submittals.

3.18.2 Overall Guidelines. The Architect/Engineer shall be responsible for:

3.18.2.1 Developing, documenting, and promoting technical discussion of these systems early in the Project. Early submittals are to include narrative technical discussion of system types, materials, and controls; including options, advantages, disadvantages, relative costs, and Architect/Engineer recommendations.

3.18.2.2 Ensuring that all major decisions regarding system types, materials, and controls are determined and agreed to by Owner/User by the end of Design Development Phase; and documented in the Design Development submittal. Costs are to be included in the Architect/Engineer's Design Development estimate of construction cost.

ARTICLE 4

DESIGN AND CONSTRUCTION DOCUMENTS

4.1 Standards for Construction Documents

4.1.1 Drawings Requirements

4.1.1.1 Drawing size shall be as determined by the University Project Manager, and shall be arranged by subject category in the format prescribed by the university. The sheets of each submittal shall be the same size. Unless otherwise defined in the Agreement or Additional Services Authorization, the record documents shall be reproduced for record purposes on plastic film (Mylar), with a minimum four mil thickness.

4.1.1.2 The title block on each drawing shall appear in lower right hand corner or along the right margin. An example of the required information is shown in Exhibit 7.

4.1.1.3 All applicable design data shall be shown on the drawings, Le., Life Safety Code, Standard Building Code data, design loads, working stresses and assumed conditions, and gross, net and volume square footage calculations.

4.1.1.4 Lettering shall be vertical uppercase and must be plain and legible; minimum size shall be 1/8". All symbols shall be clearly separated from one another and from adjacent lettering or lines.

4.1.1.5 Every plan, elevation, section, detail, etc. shall be titled, to include a scale. The scale should be given as an example of the object drawing, i.e.: scale 1/8" = 1'. Graphic scales shall be provided where appropriate.

4.1.1.6 Title sheets, title pages, and binding of documents shall be in the format shown in Exhibit 8.

4.1.1.7 All drawings shall be prepared in cad files in accordance with university requirements.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.1.2 Project Manual Requirements (to include technical specifications)

4.1.2.1 The University Project Manager will provide the Architect/Engineer with the standard State University System Instructions to Bidders, General Conditions and Special Conditions, and any applicable supplements. The Architect/Engineer shall become thoroughly familiar with these documents and incorporate additional requirements and Special Conditions as appropriate. If changes to the General Conditions are necessary, they shall be accomplished by the use of Supplementary General Conditions.

4.1.2.2 The Architect/Engineer shall prepare the Project Manual so that it complies with the requirements and customary practices of the State University System and the university for which the project is planned; and is thoroughly coordinated, complete, concise and free of redundancy. Each Project Manual should be tailored to the project and should not include provisions which are not applicable to the project.

4.1.2.3 Project Manuals shall be printed in an 8 1/2" x 11" format, bound on the left side in a permanent binder, and printed on both sides of the paper, with each section starting on the right hand side. Minimum paper weight should be 80 lb. stock. Cover stock should be a minimum weight of 90 lbs.

4.1.2.4 Technical specifications (Divisions 2-16) shall be prepared in accordance with the most recent Construction Specifications Institute Manual approved by the university. Specification sections shall be formatted in three parts: general, products and execution. Work to trades shall not be assigned in the specifications: the Conditions of the Contract establish the Contractor as responsible for all Work.

4.1.2.5 Proprietary Specifications.

4.1.2.5.1 When specific manufacturers are named, the naming of a specific manufacturer should serve only to establish a level of quality. Specifications should not be made proprietary unless there is sufficient justification, which must be well documented and specifically approved in writing by the university.

4.1.2.5.2 Use performance, descriptive, or reference standard specifications to the greatest extent possible. If a manufacturer's name is used to establish a level of quality, when possible, include three or more acceptable manufacturers which have been evaluated and found to be equal in quality to the specification. Add "or approved equal" language to product specifications which mention manufacturers by name but are not intended to be proprietary. Substitutions of equal or better quality products must be approved, prior to bid opening, as described in the General Conditions of the Contract for Construction.

4.1.2.5.3 Sole source specifications must be recommended to the university and approved by the university in writing in accordance with Section 255.04, Florida Statutes.

4.1.2.6 Augment, but do not repeat, the provisions contained in the Instructions to Bidders, Conditions of the Contract and Contract Forms. In Divisions 02 through 16, likewise do not repeat provisions contained in Division 01.

4.1.2.7 The Architect/Engineer shall maximize the use of standard materials, standard methods of construction, and standard specifications. Specifications for classification of work and materials issued by an approved association, such as ASTM, ASA, ASME, etc., may be included. Each referenced specification must be examined to ensure that it is suitable for the intended purpose. When a small quantity of materials is needed, the reference to a standard commercial product is sufficient.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.1.2.8 In referencing standard specifications, the Architect/Engineer shall: avoid reference to specific paragraphs in the standard specifications which will limit the specification; avoid repeated references to a standard specification within the same section of the specifications; and, include types, classes, weights and such characteristics to ensure accurate description.

4.1.3 Final contract documents shall bear the professional seal and signature of the Architect/Engineer.

4.2 Errors and Omissions

4.2.1 The drawings shall be prepared using the industry standard of care so that change orders to construction due to errors, omissions, inadequacies, or conflicts between various component parts or with the specifications are minimized.

4.3 Conceptual Schematic Design

4.3.1 The conceptual schematic design phase requires the development of a concept or concepts for the project. The early conceptual studies required by the agreement shall be sent to the University Review and approval. For the final Conceptual Schematic Design submittal, the Architect/Engineer shall present sufficient documentation, including perspective sketches and models, to ensure full comprehension of the design solution. Formal models and perspective renderings are not required as a Basic Service of the Agreement. The deliverable for Conceptual Schematic Design shall include, but not be limited to:

4.3.1.1 A statement confirming that the Architect/Engineer has verified the building program.

4.3.1.2 A copy of the existing campus master plan drawing showing the location of the project and a demonstration of the master plan's intent for the project.

4.3.1.3 A site plan with diagrammatic indications, showing the relationship of all components, site utilities, and circulation elements, including consideration for future site development consistent with the master plan infrastructure requirements.

4.3.1.4 Topographic studies of the terrain, emphasizing features that contribute to the solution or require significant alteration for a solution.

4.3.1.5 A description of the site, including known soil conditions, ground water conditions, zoning, accessibility, utility services, governing codes, etc.

4.3.1.6 If Section 267.061 (2), F.S., is applicable to the Project, a statement that the Bureau of Historical Preservation, Department of State, has been consulted and that any conflicts with present conservation or historical programs have been acknowledged and/or resolved.

4.3.1.7 Small scale line drawings of plans and sections adequate to define horizontal and vertical relationships of the various project components, along with sketches to define the initial concept and direction of the project.

4.3.1.8 A statement and evaluation of concepts and measures proposed to ensure energy conservation.

4.3.1.9 In the case of additions or renovations to existing buildings, a plan showing existing and proposed facilities in their relative arrangement and relationship.

PROFESSIONAL SERVICES GUIDE

Florida International University

4.3.1.10 A plan for providing total accessibility to the facility and evidence of coordination with the university ADA Coordinator and other accessibility groups. The Architect/Engineer should request ADA survey information from the University Project Manager.

4.3.1.11 A general description of architectural, engineering, and construction concepts and the architectural, structural, plumbing, fire protection, mechanical (HVAC), communications, electronics and the electrical systems to be used. If fume hoods, fume exhaust systems, 100% outside air systems, animal care facilities, clean rooms or other specialized HVAC systems are required, additional requirements apply (see Clause 4.3.1.17 and Paragraph 3.18).

4.3.1.12 A confirmation or updated statements of the building program's off-site utilities demand quantities, and discussion. The Architect/Engineer shall confirm with the University Project Manager that sufficient central utilities system source and distribution system capacity exists to serve the project. If there is an apparent shortfall in capacity to serve the project, the submittal shall include notice to that effect. The following items shall be included:

- .1 Chilled Water - estimate of tons required and identification of source of supply (package or central plant). Analysis of adequacy of off-site pipe capacity.
- .2 Steam or Hot Water Loop - estimate of BTUH required and identification of source of supply. Analysis of adequacy of off-site pipe capacity.
- .3 Electrical - Estimate of total A load and identification of source and adequacy of supply .
- .4 Potable Water and Sanitary Sewer - Identification of number of gallons per day, identification of source of water supply and method of sewage disposal. Analysis of capacity of supply and disposal sources. Discussion of any permit requirements.
- . 5 Irrigation Water - Identification of number of gallons per day required and identification of supply source. Discussion of any permit requirements.

4.3.1.13 A discussion of application of codes and required permits.

4.3.1.14 Identification of all off-site and off-campus infrastructure costs caused by the project, i.e., concurrency mitigation costs for utilities, roadways, etc. If a mitigation plan is required for the project, the Architect/Engineer may be required to develop the plan as an additional service.

4.3.1.15 A cost estimate and space analysis correlated to the program requirements and approved budgets, including any off-site and off-campus infrastructure costs. The format to be used is shown in Exhibit 6.

4.3.1.16 A current project schedule.

4.3.1.17 Where fume hood exhaust systems, 100% outside air systems or other specialized HVAC systems are provided, the Architect/Engineer's mechanical, electrical and plumbing engineers must be substantially involved in Conceptual Schematics development.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.3.1.17.1 Between effective date of the Notice to Proceed and the Conceptual Schematic submittal, the Architect/Engineer shall take the lead, promote, coordinate and participate in discussions; collect technical information; provide calculations and analysis; all as required to develop information to complete the Conceptual Schematic submittal requirements noted below.

4.3.1.17.2 Projects with laboratories and/or fume hoods: Conceptual Schematic submittal shall include:

- a) Preliminary fume hood schedule with room location; type of hood (general purpose, radioisotope, perchloric acid); size; minimum face velocity at specified open sash height (usually 16 inches or less); and, cubic feet per minute.
- b) Technical narrative of HVAC including type of fume hood exhaust system(s) to be used (central collection systems preferred, individual exhaust accepted with university/BOT approval); duct and stack materials; maximum horizontal duct diameter; types of fans with location and redundant fans noted (penthouse required for fans unless university/BOT agrees otherwise); discussion of fume hood exhaust stack with minimum exit velocity and height noted; snorkel systems; and, general exhaust systems.
- c) Technical narrative of fume hood system controls including available choices (constant volume, occupied/unoccupied for energy conservation; proposed life cycle analysis system schemes).
- d) Technical narrative of laboratory plumbing systems' including preliminary listing of all systems to be used.
- e) Technical narrative of laboratory electrical systems.

4.3.1.17.3 For Projects with 100% outside air and specialized HVAC systems, the Architect/Engineer shall provide similar information to the above; omitting what is not applicable to the Project. Clean room class per ASHRAE shall be specified (e.g., Class 10,000).

4.3.1.18 A discussion of the energy life cycle cost analysis (see Clause 4.4.1.9).

- .1 If the life cycle cost analysis is required for the project, provide a listing of the schemes to be analyzed and the rationale.
- .2 If not required, provides the rationale for the exemption.
- .3 If life cycle analysis is required and is not included in the scope of Basic Services, the Architect/Engineer shall request an Additional Services Authorization prior to performing services associated with life cycle analysis.

4.3.1.19 Central utilities systems projects. The Architect/Engineer shall include a discussion of options for systems, equipment, materials and technical options. The discussion shall include options considered, advantages, disadvantages, budget costs, and Architect/Engineer's recommendation.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.4 Advanced Schematic Design

4.4.1 The advanced schematic design phase requires the evolution of the approved concept and the deliverable shall include, but not be limited to:

4.4.1.1 A bound document describing the project, including how the design satisfies the program with sketches and drawings as needed to fully describe the interior and exterior features of the design. This presentation may include copies of drawings and materials included in the concept schematic presentation.

4.4.1.2 A plan showing how the project fits into the adopted campus master plan.

4.4.1.3 Site plans showing existing and proposed roads, walks, circulation elements, utility systems, plantings, and special site features.

4.4.1.4 Studies and reports relative to the site and its topographical, ecological, botanical and other features contributing to the solution or requiring significant alternation for a solution.

4.4.1.5 A description of existing zoning and other site conditioning factors restricting development and the solutions or recommendation for resolving them.

4.4.1.6 Floor plans (including "life safety plans"), elevations, building sections, and sketches as necessary to adequately present the concept.

4.4.1.7 If the project is an addition, or is otherwise related to existing buildings on the site, show the existing buildings and their general arrangements and relationships.

4.4.1.8 A general description, analysis, and sketches of the design and construction concepts for architectural, structural, plumbing, fire protection, mechanical (HVAC), communications, electronics and the electrical systems.

4.4.1.9 Energy life cycle cost analysis complying with State University System requirements must be conducted: a) when the project provides 13,000 or more new gross square feet or an estimated total new HVAC load of 40 tons or more; or, b) when the project includes renovation of space and new HV AC air handling units for which the load is 40 tons or more. Mechanical and electrical descriptions, including computerized building management systems, indicating proposed systems and equipment in suitable detail, accompanied by a complete schematic format shall be submitted. The analysis shall be submitted on the SUS Energy Life Cycle Cost Analysis Summary Form (see Exhibit 9). The University Project Manager will provide written direction to the Architect/Engineer on the scheme to be used in the project.

4.4.1.10 Identify total demand loads for the project to be required of the utility systems. Where it has been determined that there is a shortfall in capacity to serve the building project for any utility, the Architect/Engineer shall meet with the Owner and determine the appropriate course of action to make up the shortfall, and this course of action and the Architect/Engineer's estimate of associated design and construction costs shall be included in the Advanced Schematic submittal. Where special or energy intensive mechanical systems are considered (e.g., 100% air systems; central fume hood collection systems), provide a discussion of the systems, options, advantages, disadvantages and budget costs. These systems will usually be included in the life cycle analysis. If fume hoods, fume hood exhaust

PROFFESIONAL SERVICES GUIDE

Florida International University

systems, 100% outside air systems, animal care facilities, clean rooms or other specialized HVAC systems are required, additional requirements apply (see Clause 4.4.1.21 and Paragraph 3.18.)

4.4.1.11 Specific layouts of complex areas such as kitchens, seating, sleeping, etc.

4.4.1.12 An updated plan for providing total accessibility to the facility and evidence of coordination with the university ADA Coordinator and other accessibility groups.

4.4.1.13 Details as required.

4.4.1.14 A statement of the provisions for acoustics.

4.4.1.15 Outline specifications, using CSI format.

4.4.1.16 A cost estimate and space analysis correlated to the program requirements and approved budget, including a separate line item for funding any identified off-site utilities impact cost. The format to be used is shown in Exhibit 6.

4.4.1.17 A current project schedule.

4.4.1.18 A listing of code and permit requirements, including specific problems encountered in conforming to these codes and permits and proposed solutions, waivers and variances required or being pursued.

4.4.1.19 Recommendations regarding additional or other services required, such as: soil borings, detailed cost estimates, models and renderings.

4.4.1.20 The Document Submittal and Review checklist' using the format shown in Exhibit 10.

4.4.1.21 Where fume hood exhaust systems, 100% exhaust systems, 100% outside air systems or other specialized HVAC systems are to be provided, the following requirements apply:

4.4.1.21.1 Between the Conceptual Schematic submittal and the Advanced Schematic submittal, the Architect/Engineer shall continue discussions with Owner/User to further clarify the systems requirements, design basis and cost.

4.4.1.21.2 For Projects with laboratories and/or fume hoods, the Advanced Schematic submittal shall include:

- a) Updated fume hood schedule including room location, type of hood, size, minimum face velocity at specified open sash height, cubic feet per minute.
- b) Updated HVAC technical narrative with type of fume hood exhaust system(s) to be used (central collection systems preferred, individual exhaust accepted with university/BOT approval); duct and stack materials; maximum horizontal duct diameter; types of fans with locations and redundant fans noted (penthouse required for fans unless university/BOT agrees otherwise); discussion of fume hood exhaust stack with minimum exit velocity and likely height; snorkel systems; and, general exhaust systems.

PROFFESIONAL SERVICES GUIDE

Florida International University

- c) One-line ductwork layout including HVAC supply, ordinary exhaust, fume hood supply, fume hood exhaust and lab general exhaust systems; preliminary penthouse equipment layout, roof plan with stacks and guywires; typical stack elevation view with top of stack height.
- d) Updated fume hood system controls technical narrative (constant volume, occupied/unoccupied for energy conservation; proposed energy life cycle analysis system schemes).
- e) Updated laboratory plumbing systems technical narrative, including preliminary listing of all systems and materials to be used.
- f) Updated laboratory electrical systems technical narrative, including preliminary listing of design philosophy (one panel per lab, likely amps per panel; emergency circuits per lab; listing of known special electrical circuits needed with room and equipment to be served), emergency generator size and items served.

4.4.1.21.3 For Projects with 100% outside air and specialized HV AC systems, the Architect/Engineer shall provide, similar information to the above, omitting what is not applicable to the Project. Clean room Class shall be documented, as well as how the proposed design is to meet the ASHRAE requirements for that Class.

4.4.1.22 Central utilities systems projects. The Architect/Engineer shall include further development and discussion of the selected options and complete scope with simplified central plant or site sketches. The Architect/Engineer shall include an estimate of construction cost by major equipment line items and a discussion of this estimate with respect to the Owner's budget.

4.5 Design Development

4.5.1 The design development phase consists of the amplification and refinement of the Advanced Schematic Design. By the end of the Design Development phase, the Architect/Engineer shall have finalized all major design and equipment decisions, and the costs associated with these decisions shall be included in the Architect/Engineer's estimate of construction cost. The deliverable for this phase shall include:

4.5.1.1 Site

4.5.1.1.1 Location plots property and topographical surveys, subsurface boring logs and plans, ecological and botanical surveys, and other appropriate information.

4.5.1.1.2 A copy of the Master Plan indicating the location of the project and total scheme, if applicable.

4.5.1.1.3 Environmental considerations, including necessary design data, specifications, and cost estimates for preservation, dust, erosion, sedimentation and run-off control, where applicable, as an integral part of the design and construction project. Such controls will be limited to the areas involved in the construction operation and those requires by applicable codes and permits. Environmental control should not be confused with landscaping. The information provided will include statements regarding the type of treatments selected, the affected areas, and the reasons for the selection of the type of controls chosen.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.5.1.1.4 Grading and Site Development.

4.5.1.1.5 All permanent features to be constructed on the site.

4.5.1.1.6 All permanent roads, walks, paths, and parking lots, including a statement of the general soil conditions with a brief outline of the soil exploration and testing performed as related to the development of roads, etc. The type and volume of traffic, controlling wheel loads, classes of surfacing under consideration, with justification for same, and any deviation from criteria fitness for those classes.

4.5.1.1.7 All existing and proposed utility services including runs, locations, capacities, sources, characteristics, materials and installation methods should be fully described. The Architect/Engineer shall review the utilities sub-element of the adopted campus master plan (available from the University Project Manager) with the university and assure that planned utilities are provided in the project.

4.5.1.1.7.1 Electrical:

- .1 A statement relative to the adequacy of the primary electrical supply to the site. If the primary source is inadequate, state measures proposed to correct the deficiency.
- .2 The characteristics of the electrical supply to the site, including circuit interrupting requirements and voltage regulations.
- .3 An estimate of the total connected load and resulting kilowatt demand load (KVA) by applying proper demand and diversity factors if a group of loads is involved.
- .4 The basis for selecting a primary and/or secondary distribution voltage.
- .5 The type, size, and location of conductors.
- .6 Describe the pertinent standards of design, such as voltage drop, physical characteristics of overhead or underground circuit, types of lighting units and lighting intensities.
- .7 Electronics and Instrumentation: system engineering concepts; site and location considerations; antenna requirements such as types, separation, height, aircraft clearance, and area requirements; site communications and control linkages; electronic security considerations .
- .8 Lawn Sprinkler Systems: tentative layouts, material, sizes, etc.

4.5.1.1.8 Site drainage plans and analysis.

4.5.1.1.9 Fencing. Type, height and justification for fencing.

4.5.1.1.10 Landscaping. Plant species, size and layout. Actual full-grown canopy size shall be indicated in the plan, both for existing trees to be saved and for new trees.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.5.1.1.11 Lateral and transverse sections through the site shall indicate development of the site, when necessary, due to substantial elevation changes or circulation at more than one level.

4.5.1.1.12 Any special consideration pertinent to the site and its development.

4.5.1.2 Buildings

4.5.1.2.1 Architectural:

- .1 The plan of each floor showing movable and built-in furniture and equipment, fixed equipment, and any other use-determining factors.
- .2 Area recap and square footage should be indicated for each floor plan area and for the project in total in comparison to that required by the program.
- .3 Exterior elevations, delineating materials and noting floor elevations at each level.
- .4 Transverse and lateral sections through the building, indicating heights, vertical circulation, and relationships. The finished floor elevations of each level should be given.
- .5 Wall sections and wall details necessary to indicate the methods of construction indicating the overall values achieved as required by the Florida Energy Conservation Act, and indicating the fire ratings to be achieved.
- .6 Schedules indicating finishes and equipment, and the required flame spread ratings, etc.
- .7 A summary of code related design parameters on the drawings noting NFPA, Standard Building Code, and other required codes compliance criteria. This summary of items shall address; but not be limited to: travel distances, sprinkler requirements, ratings of fire protection, exit width requirements, building type, construction type, occupancy classification, etc.
- .8 Provide large scale plans describing complex, intensely equipped or furnished areas, and areas needing clarification.
- .9 A description of the materials used for all major components of construction.
- .10 Other information, drawings, etc. considered necessary for the development of the program or explanation of the design.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.5.1.2.2 Structural:

- .1 A description of foundation conditions, types of foundations to be used, the method by which the allowable bearing value is to be determined, and the maximum allowable bearing capacity for the foundation.
- .2 Statement as to the type of construction adopted and reasons therefore, with capacities, dimension, or other size criteria.
- .3 Plans showing framing members and column sizes, indicating special design features and noting floor elevations. The description of structural floor system proposed with length and spacing of principal members, etc.
- .4 The description of structural roof system proposed with principal members, dimension, etc.
- .5 Provide structural building sections, transverse and longitudinal, indicating vertical relationships and headroom.
- .6 Show limited load carrying capacities and statements of live loading to be used including floor loads, wind and lateral loads, earthquake, etc. with justifying data.
- .7 Provide calculations and design criteria when requested.
- .8 A statement of any special considerations that affect the design.

4.5.1.2.3 Heating, Ventilation, Air Conditioning (HVAC):

- .1 Provide floor plan showing equipment layouts and single line layouts of supply and return duct work.
- .2 Provide typical section of mechanical room showing equipment and duct work. Also include typical section of space above corridor when used for ductwork, and typical section of space above labs showing fume hood exhaust ducts.
- .3 Provide full descriptions of automated management systems proposed for use, including current and future capabilities.
- .4 If fume hoods, fume hood exhaust systems, 100% outside air systems, animal care facilities, clean rooms or other specialized HVAC system are required, additional requirements apply (see Sub-clause 4.5.1.2.13 and Paragraph 3.18).

4.5.1.2.4 Heating Systems:

- .1 Statements of indoor and outdoor design temperatures and "U" factors for walls, ceilings, floors, etc., to be used in design.
- .2 Heating medium, such as steam, hot water, gas or electric. If central plant steam/hot water source is not used, provide justification and basis for fuel selection.

PROFFESIONAL SERVICES GUIDE

Florida International University

- .3 Type of heating system such as reheat at central air handling units, perimeter terminal units with heat coils, etc.

4.5.1.2.5 Ventilation and Exhaust:

- .1 Number of air changes per hour or cfm per square foot in various areas. State basis for selection of air change rate (ASHRAE Guide and page number; Standard Mechanical Code, etc.)
- .2 Ventilation air quantity during heating season and how acquired.
- .3 ASHRAE 62-1989 outside air quantities shall be provided. The means of measuring and controlling this outside air shall be provided (such as fan and VA V box) to assure correct quantities during occupied times and reduced air handler fan speeds and provide positive shutoff during unoccupied times. The Architect/Engineer shall discuss its approach to achieve this in this submittal.

4.5.1.2.6 Air Conditioning:

- .1 Provide a brief description of the air conditioning systems considered and final system selected.
- .2 A statement of areas to be air conditioned.
- .3 Statement of inside design temperatures and relative humidity, outside wet and dry bulb design temperatures, "U" factors for the type of construction proposed and a statement of the economics of applying insulation and/or sun shades .
- .4 Description of HVAC equipment to be used inside and outside the building. Include air handling units, filters VA V boxes, terminal units, exhaust fans and any special HVAC systems. If central plant chilled water source is not used, provide justification and description of recommended solution.
- .5 Discussion of HVAC controls, including type (pneumatic only, pneumatic with DOC panel) and design philosophy. Discuss thermostat placement, special control features and justification, total estimated HVAC control system cost. Discuss any humidistat used, reason for using, and settings.

4.5.1.2.7 Refrigeration (Cold Storage):

- .1 Statement of areas to be refrigerated indicating their usage and temperatures to be maintained.
- .2 Outside design dry and wet bulb temperatures.
- .3 Type of refrigeration equipment, type and thickness of refrigeration insulation, and whether factory prefabricated cooler or cold storage box.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.5.1.2.8 Electrical:

- .1 Indicate electrical service entrance characteristics, transformer requirements, etc.
- .2 Indicate electrical characteristics such as phase, voltage, number of wires, etc. of each circuit. Provide a breakdown of the estimated connection load to show:
 - .1 Lighting and convenience outlet load.
 - .2 Power load for building equipment such as heating, air conditioning, etc.
 - .3 Loads for special operating equipment such as compressors, X-ray equipment, pumps, etc., and for power receptacle being provided to energize special equipment. Apply an appropriate demand factor to each to compute a total demand load.
- .3 Indicate the location of the main switchboard or power panels, light panels and all equipment panels.
- .4 Indicate type of wiring system, such as a rigid conduit, electrical metallic tubing, non-metallic sheathed cable, and where proposed for use.
- .5 The type of conductors such as rubber insulated, varnished cambric, lead covered, etc., and their proposed location.
- .6 Show the location of all lights, power outlets, switches, etc.
- .7 Describe the proposed pertinent standards of design such as voltage drop, lighting intensities, and types of lighting fixtures.
- .8 Describe the short-circuit duty required for all protective devices and switchgear.
- .9 Indicate the requirements for the emergency electrical system.
- .10 Ensure that the electrical information for the facility is fully coordinated with the site electrical requirements and with the low voltage communications systems requirements.
- .11 Provide any other information deemed necessary.

4.5.1.2.9 Communications, Electronic and Instrumentation Provisions:

- .1 Provide sufficient information including engineering concepts for review purposes of the systems proposed; i.e., intercom system, telephone system, public address system, radio and antenna systems, television antenna systems, protection alarm systems, respond tie-ins and any other data or systems deemed necessary.
- .2 Indicate equipment selections, including special equipment requiring development, research, or bread-board methods to meet the requirements.

PROFFESIONAL SERVICES GUIDE

Florida International University

- .3 Site or location considerations.
- .4 Required radio paths and propagation.
- .5 Antenna requirements such as types, separation, tower heights, aircraft clearance, and area requirements.
- .6 Antenna transmission lines, terminations and switching.
- .7 Bonding and grounding requirements.
- .8 Communication, control cables and radio links.
- .9 Test equipment, repair shop and spare parts storage requirements.
- .10 Equipment and instrumentation arrangement and space requirements indicating requirement for racks, consoles, and for individual mounting.
- .11 Wiring and cable requirements plus terminations.
- .12 Power and lighting requirements, including emergency or standby requirements.
- .13 Air conditioning requirements, including humidity and dust control requirements.
- .14 Interference and clearance requirements.

4.5.1.2.10 Plumbing:

- .1 Provide preliminary layout of utility lines and building construction service lines and elevations and sizes fundamental to design.
- .2 Preliminary floor plans showing major horizontal and vertical services, the location and size of fixtures, equipment and the number of persons served.
- .3 Preliminary building section showing riser and branch lines, fixtures and equipment.
- .4 Provide the estimated number of fixture units in order, demand and GPM for all plumbing fixtures.
- .5 Provide the estimated minimum and maximum water pressure at each building.
- .6 Indicate the type of heater and capacity for hot water supply.
- .7 Additional details as necessary to describe or clarify any other conditions.

4.5.1.2.11 Fire Protection:

- .1 Indicate service hydrant, stand pipe, test valve, and fire pump locations.
- .2 Indicate risers and hose cabinets.

PROFFESIONAL SERVICES GUIDE

Florida International University

- .3 For sprinkler systems, indicate the authority for the installation, the hazard rate of occupancy, the type of sprinkler system (wet or dry), and the water volume and pressure required. Delineate any special system such as carbon dioxide, foam, etc. that will be required. Verify adequacy of water supply and indicate if installation of fire pump is required. If a fire pump is required, include pump flow rate, pressure and location.
- .4 Provide any other data deemed necessary.
- .5 Indicate certification necessary for fire alarm installers, suppliers, and manufacturers.
- .6 Provide verification that the design has been reviewed with the State Fire Marshal.

4.5.1.2.12 Special Equipment:

- .1 Kitchen equipment.
- .2 Auditorium seating.
- .3 Stage curtain and equipment.
- .4 Gym layout and equipment.
- .5 Window coverings.
- .6 Hospital equipment.
- .7 Lawn sprinkler equipment systems.
- .8 Vacuum cleaning systems.
- .9 Material handling equipment.
- .10 Any other systems deemed necessary for inclusion.

4.5.1.2.13 Where fume hood exhaust systems, 100% outside air systems or other specialized HVAC systems are to be provided, the following requirements apply.

4.5.1.2.13.1 Between Advanced Schematic submittal and Design Development submittal, the Architect/Engineer shall continue discussions with Owner/User to further clarify the systems requirements, design basis and cost. The intent is for the Project Team to make all major mechanical, electrical and plumbing materials, systems and cost decisions before the Design Development submittal, and to document these decisions in the Design Development submittal.

4.5.1.2.13.2 For Projects with laboratories and/or fume hoods, the Design Development submittal shall include:

- a) Final fume hood schedule and notes, including room locations, type of hood, size, minimum face velocity at specified open sash height, cubic feet per minute, type of sash.

PROFFESIONAL SERVICES GUIDE

Florida International University

- b) Final HV AC technical narrative including type of fume hood and other exhaust system(s) to be used; duct and stack materials; types of fans with locations and redundant fans noted; discussion of fume hood exhaust stack with minimum exit velocity and height; and, snorkel systems and general exhaust systems.
- c) Provide one-line duct work layout, penthouse/mechanical room equipment layouts, roof plan and typical stack elevation view.
- d) Final fume hood system controls technical narrative.

PROFFESIONAL SERVICES GUIDE

Florida International University

- e) Final laboratory plumbing systems technical narrative including all systems and materials to be used in fume hoods and laboratories; also provide layout drawings of ordinary waste, acid waste and all plumbing systems piping; include notes at each laboratory sink location.
- f) Updated laboratory electrical systems technical narrative, including preliminary listing of design philosophy (one panel per lab, likely amps per panel; emergency circuits; special electrical circuits needed; emergency generator size and items served).
- g) An estimated construction cost which incorporates all of the above items.

4.5.1.2.13.3 For Projects with 100% outside air and specialized HV AC systems, the Architect/Engineer shall provide similar information to the above; omitting what is not applicable to the Project. Clean room Class per ASHRAE and how requirements are met shall be documented, including HEPA filters.

4.5.1.2.14 An updated plan for providing total accessibility to the facility and evidence of coordination with the university ADA Coordinator and other accessibility groups.

4.5.1.2.15 Energy and potable water savings equipment, systems and measures. The Architect/Engineer shall provide a listing of all such items incorporated into the project for additional energy and potable water savings.

4.5.1.3 Checklist. Submit a completed Document Submittal and Review checklist (Exhibit 10) and ensure that all items in the checklist have been considered.

4.5.1.4 Bid Scope. Submit a recommended base bid package and the additive alternates (deductive alternates are prohibited). Alternates shall be limited to a maximum of six (6). Under no circumstance shall any items required by code or required to make the facility functional be included as an alternate.

4.5.1.5 Probable Construction Costs. Provide an estimate of probable construction cost. This estimate shall include a comparison to the Owner's approved budget. The format for the cost estimate is shown in Exhibit 6.

4.5.1.6 Code and Permit Analysis Summary. A building-specific code and permit summary shall be included on the drawings. The summary shall include, but not be limited to: exit and fire protection requirements and calculations, building classification, occupancy, and sprinkler hazard rating. Note any special problems with conforming any codes and permits.

PROFFESIONAL SERVICES GUIDE

Florida International University

4.5.1.7 Building Classification for Energy Consumption. (The format is shown in Exhibit 6A).

4.5.1.8 A current project schedule.

4.5.1.9 The Board of Regents Cost Containment Guidelines report.

4.5.1.10 Other Data. Submit such other data as deemed necessary to explain the design concept and Design Development documents. In addition to the requirement for code data to be incorporated on the drawings, the Architect/Engineer shall submit a Summary Report containing the basic code data as outlined in Section 4.5.1.2.1.7. Other categories, including structural, mechanical, plumbing and electrical code criteria shall also be incorporated to ensure full coordination between the documents.

4.5.2 The final step of the Design Development Phase is a presentation by the Architect/Engineer in which the project design is explained in detail to the University Project Manager, other university personnel. This presentation shall include sufficient detail to demonstrate that all the requirements of the project are identified and understood and that the Architect/Engineer is fully capable of implementing the design concept in the final plans and specifications. This presentation shall also include a detailed description of the Standard Building Code and Life Safety Code data and handicapped/accessibility criteria incorporated in the documents, to ensure that all elements of design conform to statutory and required building codes. The Architect/Engineer shall respond in writing to any comments generated by this presentation as soon as possible.

4.5.2.1 The Architect/Engineer shall obtain appropriate sign-offs from user groups as determined by the University Project Manager. These shall include selection of colors, materials and finishes.

4.6 Construction Documents

4.6.1 The construction documents phase requires the Architect/Engineer to prepare contract documents in sufficient scope for bidding and construction. The deliverable for this phase shall consist of:

4.6.1.1 General:

- .1 The Document Submittal and Review checklist (Exhibit 10) indicating disposition of all items.
- .2 The Architect/Engineer's Estimate Summary and Budget Comparisons (Exhibit 6).
- .3 Color Schedules. The specifications and drawings shall indicate the actual colors or color ranges chosen to be used on the project. The Architect/Engineer shall also submit a complete listing of colors to be used, including pallets and material samples as necessary.

4.6.2 50% Construction Documents Phase. The Architect/Engineer shall submit construction documents in sufficient detail to provide scale layout of major HVAC/electrical equipment in the mechanical and electrical rooms and design detail for the components of the building. All items addressed in the Design Development documents shall be included in the construction documents. The 50% Construction Documents shall include complete draft specifications (handwritten notes and strike-

PROFFESIONAL SERVICES GUIDE

Florida International University

outs are acceptable) and preliminary major mechanical/electrical/plumbing equipment schedules. The 50% Construction Documents submittal shall also include the Architect/Engineer's Estimate of Probable Construction Cost. Upon approval of the 50% Construction Documents by the university, the Architect/Engineer may submit a request for payment.

4.6.2.1 With the submission of the 50% Construction Documents, the Architect/Engineer shall also provide a list of trades which will be involved in the Project as they are listed in the Department of Labor and Employment Security Minority Business Advocacy and Assistance Office Minority Business Enterprise Directory. This will enable the university or construction manager to invite the appropriate MBE's to the pre-bid/pre-solicitation meeting.

4.6.3 100% Construction Documents Phase. The Architect/Engineer shall submit 100% Construction Document review sets to the University Project Manager and to any other agency from which approvals are required. The submittal shall include the Architect/Engineer's Estimate of Probable Construction Cost and the Project Manual, including contract conditions regarding insurance, time of completion and liquidated damages. The University Project Manager will transmit to the Architect/Engineer any comments received from other reviewing agencies. If required, a review conference will be scheduled for the Architect/Engineer to respond to comments. The Architect/Engineer shall respond in writing to all comments and shall correct or modify the contract documents as required. The University Project Manager may ask the Architect/Engineer to resubmit the 100% Construction Documents. Upon approval of the 100% Construction Documents by the university and any other agency from which approval is required, the Architect/Engineer may submit a request for payment, and will be authorized to print the contract documents.

ARTICLE 5

BIDDING AND CONTRACT AWARD

5.1 General Contractor Projects

5.1.1 Advertising and Soliciting Bids

5.1.1.1 The Architect/Engineer shall provide bidding services as described in the Agreement and in the Project Manual.

5.1.1.2 The Architect/Engineer shall give maximum exposure of the project to all qualified bidders to encourage maximum competition. The Architect/Engineer shall solicit bids from qualified contractors by personal contact, advertisement, placement of the project in contractor and building industry reports, and distribution of documents to a plan room depository.

5.1.1.3 The Architect/Engineer shall recommend a bidding period to allow adequate time for the preparation of bids by the contractors and subcontractors. Section 255.0525, F.S., requires that construction bids be advertised for a minimum of 30 days; however, a longer period might be desirable for extremely large projects. Mondays, Fridays, and days following immediately after holidays should be avoided for receiving bids. The bid date and bid opening time will be established by the University Project Manager in consultation with the Architect/Engineer.

PROFFESIONAL SERVICES GUIDE

Florida International University

5.1.1.4 The call for bids for all construction projects will be advertised in the *Florida Administrative Weekly* thirty (30) days prior to the bid date. The University Project Manager will place the advertisement.

5.1.1.5 Upon written notice from the University Project Manager, the Architect/ Engineer may be asked to place a legal advertisement for bids with a newspaper with sufficient circulation in the project area. The advertisement is to run two times, one week apart, with the first advertisement appearing at least thirty (30) days prior to the bid date and at least five days prior to any pre-bid conference. The cost of advertising is a reimbursable expense to be handled in accordance with Paragraph 7.2.

5.1.1.6 The Architect/Engineer is responsible for distributing the drawings, specifications and addenda to bidders and other interested parties; for collecting and accounting for plan deposits and purchase monies; and for paying printing, handling, and mailing costs. Bidders should be instructed to make checks for deposits for bidding documents payable to the Architect/Engineer. The Architect/Engineer shall account for the distribution and sale of all project documents using the format shown in Exhibit 11. Costs for printing and distribution are reimbursable expenses to be handled in accordance with Paragraph 7.2.

5.1.1.7 During the bidding period, addenda shall be issued by the Architect/ Engineer to clarify or modify the construction documents as necessary. Copies of all addenda shall be transmitted to the University Project Manager. The Architect/Engineer shall not issue oral explanations to the meaning of the drawings and specifications, and oral instructions shall not be given before the award of the contract. Addenda shall be kept to an absolute minimum and shall not be used with the original issuance of the contract documents as a means of correction. Addenda shall be issued in accordance with the Instructions to Bidders section of the Project Manual.

5.1.2 Opening of Bids

5.1.2.1 The bidders are required to deliver their bids at the location specified in the contract documents. None of the parties present at the bid opening shall accept a bid after the published time of opening.

5.1.2.2 The University Project Manager will receive and open the bids. The Architect/Engineer shall attend and assist in the bid opening. The Architect/Engineer shall supply bid tabulation forms for the bidders' use during the bidding. The format for the bid tabulation form is shown in Exhibit 12.

5.1.2.3 The Architect/Engineer is responsible for completing the bid tabulation and recording the bids. The bid tabulation shall be originally prepared in ink as each bid is read aloud. The Architect/Engineer secures the signature of the University Project Manager and signs, and submits the original bid tabulation to the University Project Manager.

5.1.3 Award of Contract

5.1.3.1 The project will be awarded as described in the Instructions to Bidders in the Project Manual. The Architect/Engineer shall provide the University Project Manager with a recommendation for award of the construction contract and a Construction Contract Fact Sheet (Exhibit 13) as soon as possible after bid opening. For threshold buildings, the Architect/Engineer's recommendation for award shall be accompanied by a structural inspection plan in accordance with the Special Conditions of the Project Manual. The university president makes the contract award.

PROFFESIONAL SERVICES GUIDE

Florida International University

5.1.4 Preparation and Execution of Contract

5.1.4.1 The University Project Manager will coordinate with the appropriate university staff for the preparation of the contract, execution by the contractor and execution by the President.

5.1.4.2 The university will forward the executed contract to the contractor with a Notice to Proceed. For threshold buildings, the Notice to Proceed will be accompanied by the approved structural inspection plan. A copy of the Notice to Proceed and the contract will be provided to the Architect/Engineer and the State Comptroller.

5.2 Construction Management Projects

5.2.1 Guaranteed Maximum Price Proposal Review. The Construction Manager develops a Guaranteed Maximum Price (GMP) proposal. The Construction Manager must state any assumptions made due to unfinished construction documents. The Architect/Engineer reviews and recommends that the university approve the Construction Manager's Guaranteed Maximum Price (GMP) proposal. Recommendation of the GMP indicates the Architect/Engineer's agreement with all provisions of the GMP, including the assumptions, clarifications and qualifications, accepted value engineering recommendations, allowances, and alternates.

5.2.2 Bidding Phase Services. The Construction Manager develops trade packages for bidding to trade contractors. During the bidding period, the Architect/Engineer responds to questions regarding the construction documents and issues necessary addenda to the Construction Manager for distribution to the trade contractors.

5.2.3 Bidding Phase Payment Schedule. After execution of the GMP amendment by the university and the Construction Manager, the Construction Manager establishes a schedule for bidding the trade contracts. The schedule forms the basis of the Architect/Engineer's bidding phase payments. For example, if the 40% of the trade contracts are bid the first month, then the Architect/Engineer is eligible for 40% of the Bidding Phase payment after the first month.

ARTICLE 6

CONSTRUCTION ADMINISTRATION

6.1 General

6.1.1 The Architect/Engineer' shall provide construction administration services as described in the Project Manual. The information contained in this Guide is supplementary to the Project Manual and the Project Manual shall take precedence over the requirements of this Guide in the event of conflicts regarding construction administration services.

6.2 Construction Conferences

6.2.1 Preconstruction Conference. The University Project Manager shall arrange and chair a meeting with the General Contractor (or Construction Manager), Architect/Engineer, major subcontractors, federal

PROFFESIONAL SERVICES GUIDE

Florida International University

representatives, if federal funds are involved, and, other interested parties. If Davis-Bacon requirements are applicable (projects with federal funding), a representative of the Bureau of Job Training, Department of Labor & Employment Security shall be included. The purpose of this conference is:

6.2.1.1 To discuss requirements and responsibilities of the various parties involved to achieve expeditious handling of the construction contract.

6.2.1.2 To instruct all parties concerning required and standard procedures required submissions and federal or other applicable regulations.

6.2.1.3 To resolve all problems as to the scope of the project and signing of plans and specifications by all parties to the contract.

6.2.2 Scheduled Construction Conferences. Scheduled construction conferences will be held at regular intervals as agreed by the University Project Manager, the Architect/Engineer, and the Contractor (or Construction Manager) to cover the progress of the project. These meetings shall address, as a minimum:

6.2.2.1 Evaluation of project progress by the Architect/Engineer and the Contractor, including a comparison of current project status to the approved project schedule (to be reviewed with the University Project Manager prior to each scheduled conference).

6.2.2.2 Payment requests.

6.2.2.3 Change orders.

6.2.2.4 Special problems and remedial actions, and results of previous remedial actions.

6.2.3 Special Construction Conferences. The University Project Manager may also call special construction conferences to resolve problems or to ensure that the project is progressing in a satisfactory manner.

6.2.4 The University Project Manager, the Architect/Engineer, and the Contractor (or Construction Manager) shall attend all scheduled or special construction conferences. When required, other consultants, subcontractors, representatives of federal agencies and other parties shall attend.

6.3 Contractor's Required Submittals

6.3.1 The construction contract requires the Contractor to submit certain documents to the Architect/Engineer for review and approval. The Architect/Engineer shall submit copies of the all approved documents to the University Project Manager for processing, approval, or information as required by the Project Manual.

6.3.2 Construction Schedule

6.3.2.1 Within 30 days after the Notice to Proceed, the Contractor shall submit to the Architect/Engineer a construction schedule showing the order in which the Contractor proposes to carry on the Work, including the dates on which each task will commence, the dates for completion, and indicate the percentage of Work scheduled for completion at any given time during the contract.

PROFFESIONAL SERVICES GUIDE

Florida International University

6.3.2.2 The Architect/Engineer shall monitor the construction schedule entering the actual progress on the construction schedule at the end of each workweek or at such intervals as approved by the University Project Manager.

6.3.2.3 A copy of the updated construction schedule shall be submitted with each of the Contractor's Applications for Payment.

6.3.3 Schedule of Contract Values.

6.3.3.1 Prior to the first Application for Payment, the Contractor shall submit a Schedule of Contract Values as required by the Contract Documents.

6.3.3.2 The Architect/Engineer shall review the Schedule of Contract Values to ensure that it accurately reflects the distribution of costs in the project. The breakdown shall clearly identify cost of site work and outside utilities. The Schedule of Contract Values, approved by the Architect/Engineer (and such approval confirmed by the University Project Manager), will be the basis for evaluating the Contractor's Applications for Payment. The Architect/Engineer shall submit three copies of the approved Schedule of Contract Values to the University Project Manager.

6.3.4 List of Subcontractors

6.3.4.1 The Contractor shall submit a list of subcontractors and a list of sub subcontractors and material or equipment manufacturers to the Architect/Engineer as required by the General Conditions in the Project Manual. The Architect/Engineer shall respond to the Contractor as described in the General Conditions.

6.3.4.2 The Architect/Engineer shall ensure that the approved list of subcontractors is current at all times. On federal projects, specific forms shall be provided for this purpose. The Architect/Engineer must ensure that these forms are current and copies are provided to the University Project Manager.

6.3.5 Shop Drawings, Materials and Equipment Submittals

6.3.5.1 The Contractor shall submit shop drawings, product data and samples as required by the Project Manual. The Architect/Engineer shall take action on these submittals as described in the Project Manual.

6.3.5.2 The Architect/Engineer shall provide one copy of the shop drawings at the time of approval to the University Project Manager. The Architect/Engineer shall consult with the University Project Manager to determine the number of sets shop drawings, operations and maintenance manuals, guarantees, warranties, etc. which will be required at the completion of the project. The Architect/Engineer shall include this requirement in the project specifications.

6.3.5.3 The Contractor is required to maintain a record set of drawings, specifications, addenda, change orders, and other modifications for transfer through the Architect/Engineer to the University Project Manager upon completion of the project. The Architect/Engineer may be required to prepare a final set of Mylar reproducible or Cad record drawings. In this event, an additional services authorization must be approved by the university before this service is provided.

PROFFESIONAL SERVICES GUIDE

Florida International University

6.4 Clarification of Drawings and Specifications

6.4.1 The Architect/Engineer shall ensure that changes to drawings and specifications . prepared in response to a request by the Contractor for clarification do not change the scope of the project. Changes in scope shall be handled by change order. Clarifying drawings shall contain the statement, *If the clarifying drawings or specifications modify the scope of the basic contract, the Contractor shall notify the Architect/Engineer immediately.* Copies of any clarifying drawings or specifications and the Architect/Engineer's transmittal shall be supplied to the University Project Manager.

6.5 Applications for Payment

6.5.1 The Architect/Engineer shall meet with the University Project Manager and the Contractor to discuss handling Applications for Payment. They shall establish a day to be used for pay request cut-off. The Contractor shall be told that the request for payment must relate to the approved Schedule of Values by number. The Contractor shall be told to prepare a list of materials, including description and quantity, stored on the site at the end of the period covered in the payment request on the Contractor's letterhead. The date on this list must match the date on the certificate for partial payment. The materials covered by the request for payment may not be removed from the site after payment has been made.

6.5.2 The Architect/Engineer shall address Applications for Payment as 'Outlined in the Project Manual and shall determine that:

- .1 All information required for the request for payment is provided and properly executed.
- .2 The value of the work done or properly stored has been accurately evaluated as of the day of the cut-off.
- .3 The appropriate amount of the retained percentage has been deducted.
- .4 The correct total of preceding certificates for payment has been deducted.
- .5 Reasons for withholding payment are indicated.

6.5.3 Questions concerning the status of a contractor's Application for Payment should be addressed to the University Project Manager.

6.6 Change Orders and Construction Change Directives

6.6.1 Changes in the contracted work should be held to a minimum. The Owner will not accept offers to trade or exchange extras_ and credits. The Architect/Engineer shall determine that all changes in the work, regardless of the amount, are documented by Change Order or Construction Chang-e Directive. Change Orders - and Construction Change Directives shall be approved by the university, prior to the actual work being initiated. Where a change is made at no cost - the added and deleted work balancing - a Change Order should be prepared to record the fact that such changes were made, including a description, explanation, and monetary sums. The time extension shall be reflected on each Change Order approved. If there is no time extension, it will be noted as "0".

6.6.2 The Architect/Engineer shall prepare each Change Order and Construction Change Directive showing all the information and backup needed. Change Orders shall be supported by a written cost

PROFFESIONAL SERVICES GUIDE

Florida International University

proposal from the Contractor showing quantities and sizes of materials, unit cost, labor, profit and overhead; and a narrative justification. A Change Order shall be signed by the Architect/Engineer and the Contractor; Construction Change Directives shall be signed by the Architect/Engineer.

6.6.3 The Architect/Engineer shall submit each Change Order and Construction Change Directive to the University Project Manager for approval. The Architect/ Engineer shall maintain a log of all Change Orders and Construction Change Directives processed, indicating status and action.

6.6.4 The University Project Manager will determine that each change order is complete and secure the required approvals. The University Project Manager will distribute copies of the fully executed and approved Change Order to the Architect/Engineer, Contractor, and State Comptroller.

6.7 Claims

6.7.1 The Architect/Engineer shall handle claims as described in the Project Manual. The Architect/Engineer shall make reasonable efforts to resolve a claim, including involving the University Project Manager in resolution discussions.

6.8 Beneficial Occupancy

6.8.1 Only in extraordinary cases shall beneficial occupancy be permitted prior to substantial completion of the project.

6.8.2 Beneficial occupancy shall not occur until after an inspection and preparation of a punch list, identifying all remaining work to be performed by the Contractor. The Architect/Engineer shall submit the following to the University Project Manager:

- .1 Written approval of the Architect/Engineer .
- .2 Written approval of the Contractor to occupy all or any portion of the project before formal acceptance by the Owner. This approval shall contain a statement from the Contractor that occupancy prior to acceptance by the Owner does not violate the provisions of the contract, that no liabilities are created, and that no unwarranted delay of contract requirements is created.
- .3 Written approval of the State Fire Marshal.
- .4 Written approved from the insurance resident agent that the builders' risk coverage provisions will not be violated.
- .5 Written agreements between the University and the Contractor pertaining to the payments for the utility costs during the period of occupancy.
- .6 Written acceptances from the Architect/Engineer for the areas proposed for occupancy.
- .7 Written notices to the State Fire Insurance Fund by the University implementing insurance coverage for the building and its contents.
- .8 A copy of the punch list identifying all work remaining to be completed in the area to be occupied.
- .9 Any other items required by the Architect/Engineer or the University Project Manager.

PROFFESIONAL SERVICES GUIDE

Florida International University

6.9 Substantial Completion

6.9.1 The Architect/Engineer shall schedule the substantial completion inspection in consultation with the University Project Manager, and send notices of the date and time to the University Distribution List. The Architect/Engineer shall perform activities related to substantial completion as described in the Project Manual.

6.9.2 The Architect/Engineer shall prepare a list of all items of work not acceptable at the time of inspection and provide a list of required corrections for each trade, including provisions for indicating satisfactory correction at a subsequent inspection. The Architect/Engineer shall not certify Substantial Completion if the punch list items cannot be realistically completed within the additional days allotted for Final Completion (usually 30).

6.9.3 The Architect/Engineer shall prepare the Certificate of Substantial Completion, and submit four copies of the executed forms and three copies of the punch list to the University Project Manager. *The substantial completion date must be the same or earlier than the substantial completion date established by the Owner/Contractor Agreement, as amended by approved change orders granting extensions of time.* The Architect/Engineer shall submit a reconciling change order which justifies any extensions of time beyond that approved by earlier change order and recommend action relating to liquidated damages. The Architect/Engineer should not sign the Substantial Completion Certificate unless the State Fire Marshal has certified occupancy of the facility.

6.9.4 Official occupancy of the project shall not occur until substantial completion has been declared by the Architect/Engineer and approved by the university.

6.10 Final Completion

6.10.1 The Architect/Engineer shall schedule a final inspection in consultation with the University Project Manager and send notices of the date and time to the Owner's Distribution List.

6.10.2 The Architect/Engineer shall provide the Contractor with a list of any additional requirements for corrective action resulting from this inspection and make additional inspections, as necessary, to ensure that the work is completed.

6.10.3 The Architect/Engineer shall prepare the Certificate of Contract Completion and secure the signature of the Contractor. The substantial completion date on the Certificate of Contract Completion must be the same as the date shown on the Certificate of Substantial Completion.

6.10.4 The Architect/Engineer shall forward four copies of the Certificate of Contract Completion to the University Project Manager for processing. The University Project Manager will attach the Certificate of Contract Completion to the Contractor's final request for payment when the payment is approved for processing.

6.10.5 The Architect/Engineer shall submit the required copies of all shop drawings, as built drawings, operation and maintenance manuals, warranties, and guarantees to the University Project Manager.

6.11 Post-Occupancy Inspection

6.11.1 The Architect/Engineer shall schedule a post-occupancy inspection 45 days prior to the expiration of the one-year general warranty period with the University Project Manager. The Architect/Engineer

shall ensure that this inspection covers all phases of the constructed facility. The Architect/Engineer shall prepare a report describing all items found to be deficient and requiring corrective action.

6.11.2 The Architect/Engineer shall provide the Contractor with a list of the items requiring correction.

ARTICLE 7

ADMINISTRATIVE APPLICATIONS

7.1 Additional Service Authorizations

7.1.1 The Architect/Engineer may be asked to provide services which were not included as part of Basic Services in the Agreement. Additional Services are listed in the Agreement. Often, services which are typically considered beyond the scope of Basic Services are negotiated into the original agreement and then treated as a part of Basic Services. The Architect/Engineer shall provide **no** services which are not included as part of Basic Services until it has received an Additional Service Authorization from the university. Any additional work provided prior to such authorization is not eligible for compensation.

7.1.2 When professional services not included in the Basic Services are needed, the Architect/Engineer shall discuss this service with the University Project Manager. The Architect/Engineer shall then submit a proposal to the University Project Manager. If a portion of the services will be provided by consultants to the Architect/Engineer, then the consultants' proposals must also be provided.

7.1.2.1 If the exact scope of work necessary to complete the additional service cannot be determined, the Architect/Engineer should request a not-to-exceed amount. Not-to exceed authorizations may be billed monthly upon submittal of a detailed invoice, including timesheets, receipts, etc. The university will be the final authority as to whether an Additional Service Authorization will be issued as a lump sum or as a not-to-exceed amount.

7.1.2.2 Additional services shall be based on the maximum hourly rates established during the contract negotiation. Maximum hourly rates are listed by personnel category, i.e., Principal A/E, Registered A/E, Designer, Drafter, etc (A principal is a person who has part ownership, control and contracting authority in the firm, and for which evidence can be provided for verification purposes.)

7.1.2.3 If the fee curve can be used, a lump sum amount for the additional service may be determined. If the fee curve cannot be used, but the Architect/Engineer and University Project Manager can agree on the required scope, a lump sum can be developed, provided the Architect/Engineer's proposal and any involved consultants' proposals include a breakdown of hour's required and hourly rates. Lump sum authorizations may only be billed upon completion of pre-determined phases and approval of corresponding deliverables. These phases and deliverables should be identified in the Architect/Engineer's proposal.

7.1.2.4 The Architect/Engineer's proposal must identify whether the request is for a lump sum or a not-to-exceed authorization. The proposal shall include the proposed schedule for provision of services and proposed deliverables.

PROFFESIONAL SERVICES GUIDE

Florida International University

7.1.2.5 Permitting costs may be included in an Additional Service Authorization to the Architect/Engineer. Before including such costs in its proposal, however, the Architect/Engineer should consult with the University Project Manager to ensure that the permitting or review agency has statutory authority to charge state agencies for its permit or review.

7.1.2.6 If the supporting documentation for an additional service request is extensive, the Architect/Engineer may be asked to provide four copies of the documentation.

7.1.3 The University Project Manager will review the proposal and, upon approval, will issue an Additional Service Authorization.

7.1.4 Occasionally, the scope of an authorized Additional Service may increase. When the work required is expected to exceed the authorized scope, the Architect/Engineer must send a proposal to the University Project Manager requesting a revision to the Additional Service Authorization. The Architect/Engineer shall not provide any additional services which exceed the scope and the amount of the Additional Service Authorization until a written revision to the Additional Service Authorization is issued by the university.

7.1.5 Additional Services for prolonged contract administration shall be determined as follows: $((A.- B) \times 0.8) \times C = \text{Additional Service amount.}$

A = the original contract fee for construction administration

B= the number of days in the original construction contract

0.8 explanation - The original contract administration fee includes the heavy workload at the beginning of the construction phase (shop drawing review, etc.) and the heavy workload at the end of the construction phase (substantial completion. inspection, punch list development, final completion, etc.) The factor of 0.8 recognizes that these efforts have already been considered in the fee, and the prolonged portions of the construction phase are the days in the middle of the construction period.

C = the actual number of construction days, minus the total of [the number of days in the initial construction contract, plus any days added by change order for which the Architect/Engineer was compensated by an Additional Services Authorization]

7.1.6 If the Architect/Engineer recommends that a detailed cost estimate be conducted, the Architect/Engineer shall bear 25% of the cost for the detailed estimate. This recognizes the fact that the Architect/Engineer is responsible for cost estimates as a part of Basic Services, and a cost estimator will instead be providing those services. The 8% administrative markup is not applicable to cost consultants when the detailed estimate is being conducted at the Architect/Engineer's request. If the Architect/Engineer does not recommend these services, but the university requests them, then the Owner will bear the entire cost of the cost estimator and the Architect/Engineer will provide its own independent cost estimates.

7.1.7 The Architect/Engineer shall invoice for Additional Services as described In Paragraph.

7.2 Reimbursable Expenses

7.2.1 The Architect/Engineer must receive an Additional Service Authorization from the university

PROFFESIONAL SERVICES GUIDE

Florida International University

before incurring a reimbursable expense. The only exception to this requirement is printing bid documents, placement of a legal advertisement for construction, or payment of Fire Marshal fees. (Note: Only the printing of bidding documents is considered an automatically authorized reimbursable expense. Additional printing of review sets for the Owner during design must be authorized in advance as an additional service as described in Paragraph 7.1. Documents printed for the Architect/Engineer's own use, Owner's review sets required by the Agreement, and the bidding sets required by the Agreement are not reimbursable.)

7.2.2 Items such as general telephone, photocopying, fax and postage costs are not considered reimbursable expenses, because they are included in the Basic Services fee derived from the fee curve or in the multiplier for Additional Services or in the hourly rates for Campus Service Architects/Engineers. Except postage and handling costs for bid documents, these items may be reimbursed only under unusual circumstances; in order to be eligible for payment, the expenses must be authorized in advance by an Additional Service Authorization. The Architect/Engineer must submit a proposal to the University Project Manager which describes why the expenses are unusual and establishes a not-to exceed amount. An Additional Service Authorization would then be issued.

7.2.3 Travel expenses are only reimbursed when travel is required to perform an Additional Service; in which case, the travel and per diem costs must be included in the proposal for Additional Services. Any travel required to fulfill the requirements of Basic Services is to be provided as a part of Basic Services.

7.2.4 The Architect/Engineer shall invoice for Reimbursable Expenses as described in Paragraph 7.3.

7.3 Invoicing

7.3.1 General Requirements

7.3.1.1 The State University System is required by Section 215.422, Florida Statutes, to approve all invoices for acceptable, undisputed services, with a goal of making payment within 40 calendar days from receipt of invoice. The Architect/Engineer is requested to assist in the achievement of this goal by ensuring that all invoices are properly prepared and contain the required supporting documentation. Due to the high volume of invoices received, no invoice will be held until a work product is not corrected, nor will major deficiencies in the invoices themselves be corrected. In these cases, the invoice will be returned to the Architect/Engineer with instructions for resubmission.

7.3.1.2 All invoices shall be submitted to the university on the SUS Standard Invoice Form, included as Exhibit 14. The Architect/Engineer shall submit a signed original and three copies, including a complete set of backup documentation for three of the four invoices.

7.3.1.3 Invoices shall be numbered consecutively beginning with Number 1, and continuing in numerical order throughout the life of the contract. If an invoice is received by the university which is not numbered consecutively from the last approved invoice, it will be renumbered. For example, if invoice No. 12 is returned unpaid, and the Architect/Engineer submits invoice No. 13 prior to correction and approval of invoice No. 12, the university will renumber invoice No. 13 to No. 12.

7.3.1.4 All authorized services and expenses for the life of the project shall be indicated on the invoice form, as additional services are authorized, they should be added to the invoice form. The Basic Services are to be listed as provided on the payment schedule in the Agreement. Additional Services are to be listed in consecutive order by authorization number. Reimbursable expenses are listed either as

PROFFESIONAL SERVICES GUIDE

Florida International University

Printing Bid Documents or Legal Advertisement. A sample completed invoice is included as Exhibit 15. With the exception of printing bid documents and legal advertisement expenses, no items shall be included on the invoice which has not been authorized either by the Agreement or an Additional Service Authorization.

7.3.1.5 Invoices should not be submitted until the review period has passed following delivery of the required work product to allow the Owner's review.

7.3.1.6 To expedite payment, the number of invoices submitted should be kept to a minimum, combining as many items as possible on each invoice. No more than one invoice may be submitted per month.

7.3.2 Supporting Documentation Required: In order to comply with the State Comptroller's rules promulgated to meet the requirements of Section 287.057, Florida Statutes, supporting documentation described is required for approval of invoices, as follows:

7.3.2.1 Supporting documentation should be organized to correspond with the order that the items being requested for payment appear on the invoice.

7.3.2.2 Basic Services:

.1 Design Phases: The work product specified in the Agreement must have been submitted and approved prior to the invoice. No other supporting documentation is required.

.2 Bidding Services: Bidding services are only payable when the project is bid within the budget. If a project must be rebid due to the fault of the Architect/Engineer, the fee for Receipt of Bids will not be paid until the project has been successfully bid. The Architect/Engineer shall have submitted the items required by Article 5 of this Guide prior to invoicing, including the recommendation of award, Construction Contract Fact Sheet (Exhibit 13), and if required, the approved threshold inspection plan.

.3 Construction Administration Phase: Construction administration services are paid monthly *in* proportion to payments made to the Contractor. The amount to be invoiced is determined using the Contractor's Certificate of Partial Payment. The "Adjusted Contract Amount" is divided into the "Completed to Date" amount to determine the percentage completed. The resulting percentage is then applied to the total Construction Administration fee to determine the amount due each month. The Architect/Engineer shall also include a copy of the current Construction Phase Status Report (Exhibit 3).

- (a) The fully executed Contractor's Certificate of Partial Payment is required as supporting documentation for each monthly invoice.
- (b) The request for 100% of the Construction Administration fee must be accompanied by the fully executed Certificate of Contract Completion.

A Post Occupancy Inspection: The fee for post occupancy inspection is paid upon receipt of the post occupancy report as described in Paragraph 6.11 herein.

PROFFESIONAL SERVICES GUIDE

Florida International University

7.3.2.3 Additional Service Authorizations based one Lump Sum: The work product specified in the authorization must have been submitted and approved prior to the invoice. A copy of the authorization is required as supporting documentation. Unless phased payments are provided for in the authorization, the invoice may not be submitted until the total services have been completed.

7.3.2.4 Additional Service Authorizations based on a Not-to-Exceed Amount: These additional services may be billed monthly upon presentation of a detailed invoice. Supporting documentation includes a copy of the authorization and the following documentation, as applicable:

- .1 Labor costs (for both the Architect/Engineer and consultants) shall be supported by time sheets, indicating the individual's name, specific days, hours and tasks performed. Show calculations performed when applying the multiplier and totaling costs. Labor is only compensated for actual hours worked. Overtime rates are not allowable unless specifically requested and approved in the Additional Service Authorization.
- .2 Consultants costs must be also supported by a copy of the consultant's invoice. The invoice must be marked "approved" and signed by the Architect/Engineer.
- .3 Travel costs, when included in an authorization, may only be compensated within the limits provided in Section 112.061, Florida Statutes, which may be found on the Internet at the address, www.leg.state.fl.us. Each payment request for travel expenses will require a completed Travel Reimbursement Form, included as Exhibit 16. Mileage shall be in accordance with the official Department of Transportation map mileage. Receipts for lodging, airplane, bus, tolls, parking, taxis, rental cars, etc. must be included for each item invoiced. Receipts must be legible.
- .4 Permitting costs must be supported by a copy of the invoice from the permitting authority indicating the type of permit.

7.3.2.5 Reimbursable Expenses:

.1 Printing Costs:

(a) The Architect/Engineer may only invoice for printing costs when the project has been successfully awarded to a bidder. If the project cannot be awarded due to a fault of the Architect, however, the Architect/Engineer may invoice for printing costs.

(b) Invoices for printing of bidding documents must be supported by a completed Document Distribution Record (Exhibit 11) and a completed Contract Documents Cost Recap Sheet (Exhibit 17).

(c) Receipts for all printing, copying and mailing costs. Receipts must be legible. Figures included on the Contract Documents Cost Recap Sheet must be supported by highlighted figures on the receipts, and attaching an adding machine tape which supports the individual figures and overall totals.

.2 Advertising Costs: An invoice for advertising costs must be supported by a copy of the text of the advertisement, a copy of the invoice from the newspaper and a statement from the newspaper certifying the legal ad was published.

PROFFESIONAL SERVICES GUIDE

Florida International University

7.3.3 Past Due Billings: If there are past due billings when the next invoice is prepared, do not invoice for those services a. second time. Include these amounts in the "Less Previously Billed" column. Inquiries concerning the status of an invoice should be directed to the university.

7.3.4 Invoice approval process: Invoices are submitted to the university. After approval, a voucher is prepared and sent to the State Comptroller's Office. The State Comptroller processes the voucher, cuts the warrant and sends it to the University for Transmittal to the Architect/Engineer.

PROFESSIONAL SERVICES EVALUATION

UNIVERSITY: FLORIDA INTERNATIONAL UNIVERSITY
 Project Number: _____
 Project Title: _____
 Firm: _____
 Joint Venture: _____
 Managing Office Location: _____
 Project Manager: _____

Date: _____
 Semiannual _____
 Project Closeout _____
 Special (See Remarks) _____

BASIC CRITERIA: (Completed for all evaluations)

Quality of Technical Services (Firm listed above)

*Weight = 5 if consultants are used on project.

Value	Weight	Extension
4.0	x 5.0 * =	20.0

Consultants:	Specialty	Rating Value
	Mechanical Engineering	NA
	Electrical Engineering	NA
	Structural Engineering	NA
	Civil Engineering	NA
	Landscape Design	NA
	Building Type Specialty	NA

Average

	x 4.0 =	
--	---------	--

Timeliness of Service _____
Quality of Technical Documentation _____
Cooperation/Concern for FIU interests _____
Administration of Project Paperwork _____

4.0	x 3.0 ** =	12.0
	x 3.0 =	0.0
	x 2.0 =	0.0
	x 2.0 =	0.0

Post Occupancy Services

**Note: If post occupancy services is graded alone the weight for each part will be 10 instead of 5.

PART A: (Completed when applicable)

Achievement of Study, Program, or Design Objectives

0.0	x 5.0 ** =	0.0
-----	------------	-----

PART B: (Completed when applicable)

Administration/Enforcement of Contract Documents

**Note: If post occupancy services is graded alone the weight for each part will be 2.5 instead of 5.

0.0	x 5.0 *** =	0.0
-----	-------------	-----

Total Weight Points=	32.0
----------------------	------

Numeric Rating (Total Weighted Points/5) =	6.4
--	-----

Overall performance during the rating period is evaluated as :

REMARKS: (Completed for all evaluations)

Note: Individual category rating values are assigned using the following scale: 4 =Outstanding (Notably exceed contract requirements), 3 = Above Satisfactory (Exceeds contract requirements), 2 = Satisfactory (Meets contract requirements), 1 = Less Than Satisfactory (Less than full contract compliance).

RATED BY: _____

REVIEWED BY: _____

Title: FC Project Manager

Title: Director, Facilities Construction

This form is to be completed on the Architect/Engineer's letterhead

TO: **(University Project Manager's Name & Address)**
RE: **PLANNING AND DESIGN STATUS REPORT NUMBER**
For the Month of _____
Project Number: **BT-** _____
Project Title: _____

PHASE : *(Insert applicable phase designation and provide comments relative to the development of this phase, a statement as to the current status of the project and of phase last completed).*

PROGRAM STATUS: *(Indicate any authorized or pending changes to the program including date of authorization).*

CONSTRUCTION BUDGET:
Program \$ _____
Changes \$ _____ *(List each approved budget change including date of authorization.)*
Current \$ _____

CONSTRUCTION ESTIMATE: Current \$ _____ *(If the current estimate exceeds the current approved budget, state what measures are being taken to return the project to within the budget amount approved.)*

SCHEDULE: *(Indicate the percentage ahead or behind the approved schedule. Attach a copy of the updated schedule to the report.)*

PERMIT AND APPROVAL ACTION: *(Describe the action and efforts pertaining to acquisition of necessary permits and approvals.)*

ACTION REQUIRED BY UNIVERSITY:

ACTION REQUIRED BY THE BOARD OF TRUSTEES: *(Describe all actions that are required, either pending or late.)*

ACTION REQUIRED BY OTHERS:

REMARKS:

(Signature)

(Title)

(Date)

This form is to be completed on the Architect/Engineer's letterhead

TO: (University Project Manager's Name & Address)
 RE: CONSTRUCTION STATUS REPORT NUMBER
 For the Month of _____
 Project Number: BT-_____
 Project Title: _____

CONTRACTOR: Name: _____
 Address: _____

CONTRACT STATUS:

<u>CONTRACT SUM:</u>		<u>CALENDAR DAYS</u>	<u>SUBSTANTIAL COMPLETION DATE</u>
\$ _____	Original Contract	_____	_____
\$ _____	NTP <u>(date)</u> Change Orders to date <i>(list; attach additional Pages if necessary)</i>	_____	_____
\$ _____	Current Contract	_____	_____

% Scheduled to be Completed	_____ %	% Ahead	_____ %
% Time of Contract Elapsed	_____ %	% Behind	_____ %
% Actually Completed	_____ %		

PENDING CHANGES:

WORK STATUS: *(General description of work being performed including number of workers on site, weather, materials stored, etc., and its overall progress. List any factors contributing to failure to meet the construction schedule.)*

GENERAL CONDITION CORRECTION: *Performance of requirements under the General Conditions. Include a brief statement whether contractor is or is not complying with the various requirements of General and Special Conditions of the contract.*

DEFICIENCY CORRECTION: *Action by contractor to correct deficiencies noted in your last report. If corrective action has not been taken, give explanation.*

SITE VISITS:

(Insert number of site visits this month)

Architect (RA)	_____
Structural Engineer (PE)	_____
Mechanical Engineer (PE)	_____
Electrical Engineer (PE)	_____
Other Staff (Identify)	_____

Date _____ A/E Representative _____
 Title _____

**LAND SURVEY
REQUEST FOR PROPOSAL**

PROJECT: _____

PROJECT NUMBER: _____

DATE: _____

OWNER: _____
(Name, Address)

ARCHITECT/ENGINEER: _____
(Name, Address)

TO: _____ *(SURVEYOR)*

Please submit a proposal for: *(Describe Project)*

TIME: The survey shall be completed and delivered to the Architect/Engineer by:

USE OF DRAWINGS: It is understood that the Owner, or the Architect/Engineer, may reproduce the drawings and distribute the prints in connection with the use of disposition of the property without incurring obligation for further payment.

COST: The cost of the survey, including the drawings, establishment of site benchmark(s), and placing of property corner markers as required, shall be:

_____ A lump sum (requires a detailed proposal, including hours and hourly rates).

_____ A maximum sum (not-to-exceed), per rates in the attached categories (attach schedule of desired rate categories).

BILLING FOR THE SURVEY shall be to the Architect/Engineer, in duplicate, at the above address.

Sincerely,

(Signature)
Typed name and Title

DIVISION OF STATE FIRE MARSHAL

PLANS REVIEW FEES, PROCEDURES AND REQUIREMENTS

The plans for all construction of any new state owned or state lease building and renovation or alteration of any existing state owned or state leased building are subject to review and approval of the Division of State Fire Marshal for compliance with the Uniform Fire Safety Standard prior to commencement of construction or change of occupancy. The Division of State Fire Marshal may inspect state owned and state leased spaces as necessary prior to occupancy or during construction, renovation, or alteration to ascertain compliance with the uniform fire safety standards as per Florida Statutes 633.085 and 4A-52., Florida Administrative Code.

PLANS REVIEW FEES:

State Owned Buildings:

The fee for plans review of **ALL** contract documents, new construction or renovations to existing buildings, shall be paid by the **Design Professional** and sent along with the contract documents.

Make Checks Payable To: Department of Insurance

Fill in the memo portion of the check with “**SFM Plans Review Fee**”

The **Design Professional** shall send two (2) complete sets of signed and sealed contract documents and one set of specifications to:

If Sending By Regular Mail:

Division of State Fire Marshal
Plans Review Section
200 East Gaines Street
Tallahassee, FL 32399-0342

If Sending By Overnight Service/Hand Delivery:

Division of State Fire Marshal
Plans Review Section
325 John Knox Road, Atrium Building
Tallahassee, FL 32303

The fee for plans review is determined by multiplying the estimated construction cost of the building, by the constant .0025 (1/4%). The minimum fee is \$100.00. This does not include the cost of the land, site improvements, civil work or furniture & equipment.

Example:

$\$2,000,000.00 \times .0025 = \$5,000.00$ fee.

In situations where the state agency's own facilities prepare the construction documents, the user agency is responsible for paying the fee in advance by Samas – Journal Transfer. Our Samas Account number is: 46-10-2-39300146010000-00-000100-00; type and class code (14/10). (Benefiting Code #001000). A copy of your journal transfer (voucher) is to accompany

**EXHIBIT 5
(Con't)**

the plans. Complete attached Review Request Form, in its entirety, and include it with the plan submittal to the State Fire Marshal's Office.

State Leased Buildings:

The fee for plans review of **ALL** contract documents, (new construction or renovations to existing buildings), shall be paid **in advance by the Lessor** prior to the review of the documents.

Make Checks Payable To: **Department of Insurance**
Fill in the memo portion of the check with "**SFM Plans Review Fee**"

The **Lessor** shall send two (2) complete sets of signed and sealed contract documents and one set of specifications to:

If Sending By Regular Mail:

Division of State Fire Marshal
Plans Review Section
200 East Gaines Street
Tallahassee, FL 32399-0342

If Sending By Overnight Service/Hand Delivery:

Division of State Fire Marshal
Plans Review Section
325 John Knox Road, Atrium Building
Tallahassee, FL 32303

A copy of the cover letter is to be sent to:

Rose Cook, Chief
Bureau of Property Management
Knight Building, Suite 110
Tallahassee, Florida 32399-0950

The fee for plans review is determined by multiplying the estimated construction cost of the renovation to be leased to the State by the constant .0025 (1/4%). The minimum fee is \$100.00. If it is a new building the fee is .0025 (1/4%) of the building construction cost.

Example:

\$1,000,000.00 x .0025 = \$2,500.00 fee. If the lease is for existing space that does not require any renovations in order to occupy then you are required to fax a request for building site inspection to the Tallahassee office (Fax – (850)922-2553) requesting a site inspection for the code violations (Please include the lease number).

Plans Submission:

The Division of State Fire Marshal will require the submitter to furnish two sets of signed and sealed contract documents and one set of specifications for review to the Plans Review Section. The submitter may, however, submit plans and an earlier stage, i.e., Design Development, in which case only one unsigned set needs to be submitted. When the documents are approved for construction, one set will be stamped "APPROVED" and returned to the submitter. The stamped set of plans must be kept on the job site for the fire safety inspector's use at the time of inspection. It shall be the responsibility of the submitter to see that the "approved" set of plans is on the construction site before work begins and remains there until final inspection and approval has been issued. Plan approval is good for one year from the date of issue. The construction contract must be let within this period or the approval will expire and the plans must be re-submitted with another review fee.

The editions of the pertinent codes that will apply to your project will be those that are adopted at the date of your first submittal, regardless of phase, i.e. Design Development's 50% or final, and will not change even if a newer edition is adopted during the review process. However, if more than one year elapses between submittals, i.e., Design Development's to final, the process starts again with another fee and with current codes.

Any change orders or redesign during construction that affect life safety shall be submitted for review with the State Fire Marshal's file number indicated. There is no additional fee required for changes.

The review process allows 30 calendar days for review of all state-owned property and 10 calendar days for review of state leased property. The process seldom takes the entire required time. In an effort to help expedite the review, pleas consider the following questions:

1. Do your plans show the use of each room? (i.e.: office, conference, laboratory, closet, storage, and etc.)
2. Do your plans show the number of floors in the building and the location of the project under consideration in comparison to the entire floor and building?
3. If the building is sprinklered, do your plans show the location of the sprinkler heads in the area(s) under consideration?
4. Do your plans show the exit marking(s)?
5. Is there emergency lighting? If so, what is the type and location?
6. What is the type and location(s) of the fire extinguisher(s)?
7. Are there any special fire extinguishing systems such as Halon 1301 or a dry chemical hood system?

**EXHIBIT 5
(Con't)**

8. If applicable, do your plans show the type and location(s) of smoke and/or heat detector(s) (Including duct detection)?
9. Are there any manual fire alarm pull stations? If so, where are they located and what is their elevation above the floor.
10. Are there any smoke dampers? If so, what is their type and locations(s)?
11. Do your documents show the door fire rating on the schedule?
12. Do your plans show a nationally tested wall assembly detail for rated walls?
13. Do your plans show the exits and their exit discharge? (i.e.: top of structure to the level of exit discharge)?
14. If applicable, do your plans show the stair and handrail detail?
15. What are the interior finishes? (i.e.: paneling, drywall, wallpaper, etc.) and their flame spread ratings.

While answering these few questions will expedite the process, they are not the complete set of questions that could be asked. If there are any special circumstances or hazards that require further clarification, the reviewer will attempt to contact you; therefore, please include the name and telephone number of a contact person with your plan submission. Please remember that if you are called and asked for additional information or clarification, the reviewer needs this information in writing before he can approve the project. If the statutory time (10 days on a lease or 30 days on state owned) expires he must disapprove the project and a re-submittal process may add further delay to the project.

The following items are areas where we must have your assistance. Please ensure that all submittals address these necessary items where applicable and help us prevent lost time due to disapprovals based on lack of information.

1. **Renovation or Alteration:** Any alteration or any installation of new equipment shall be installed under the requirements of new construction. The areas shall be identified clearly, and shall show the area of concern in relation to the total building. This will ensure that the proposed renovation or alteration will not diminish the life safety components of the building.
2. **Equivalency Concepts:** Any requirement of the code that a designer wishes to modify by alternative arrangements shall in no case afford less safety to life than the code presently requires. Any request to use equivalency concepts will only be considered when technical documentation is submitted.

EXHIBIT 5
(Con't)

3. **Classification of Occupancy:** Plans shall indicate the type of occupancy based on N.F.P.A. 101, Chapter 4. See F.A.C. 4A-3 for the current edition.
4. **Change of Occupancy:** The designer shall identify the existing type of occupancy and clearly identify the new occupancy use and areas.
5. **Floor Area:** The gross square footage of the building shall be indicated on the plans. All assembly rooms shall indicate the net floor area.
6. **High Hazard Area:** Any areas of a building structure, or parts thereof, containing highly combustible, flammable, explosive products or materials which are likely to burn rapidly shall be identified on the submittal. The designer shall identify amounts and types of hazardous materials used throughout the facility.
7. **Means of Egress:** All three components of the means of egress (exit access, exit and exit discharge) shall be clearly identified. Travel distance to exits shall be detailed.
8. **Occupant Load:** The occupant load for each floor and calculations showing how the load was obtained shall be shown. All assembly rooms, spaces, or areas shall be identified and calculated with calculations shown on plans.
9. **Construction Type:** The type of construction shall be identified as per N.F.P.A. 220. See F.A.C. 4A-3 for the current edition.
10. **Atrium:** Any building in which the designer has incorporated an atrium shall have the atrium area clearly defined on the contract document.
11. **Penetration of Smoke or Fire Barriers:** Passage of pipes, conduits, bus ducts, cables, wires, air ducts, pneumatic ducts and similar service equipment through smoke and/or fire barriers shall be detailed on the contract documents.
12. **Fire Detection, Alarm and Communication Systems:** All existing or new systems shall be clearly identified on the plans. The type of system and the appropriate N.F.P.A. standard which was used for the design and installation shall be indicated on the plans and signed and sealed by the Engineer of Record.
13. **Automatic Sprinkler System, Standpipes and Fire Pumps:** All existing or new systems shall be clearly identified on the plans. The type of system and the appropriate N.F.P.A. standard which was used for the design and installation shall be indicated on the plans and signed and sealed by the Engineer of Record. Hydraulic calculations also signed and sealed by the Engineer of Record, shall accompany the plans where applicable.
14. **Correction Facilities:** The use condition of the area shall be clearly identified as per N.F.P.A. 101, Chapter 14 & 15.

EXHIBIT 5
(Con't)

15. **Lease Spaces:** If the leased space is on a floor located above the level of exit discharge (LED) a plan of the LED is required to be submitted to ensure proper existing from the building.
16. **All sheets have the correct name of the facility: Building Number, Office/Complex Name, Street Address, City, County, and Zip Code, and any assigned lease number noted on the document.**

If there are any question concerning this notice, please contact the State Fire Marshal's Plan Review Section in Tallahassee at (850) 922-3171.

Construction Inspections:

The review fee will cover plans review and up to two (2) construction site inspections, one at approximately 65% (before covering walls and ceilings) of completion, and a final inspection prior to occupancy. The intermediate (65%) inspection is optional at our discretion, and depends upon the size and complexity of the construction project. The purpose of construction site inspections is to ensure that the project is in fact constructed in accordance with the approved construction documents.

Any re-inspection required as a result of deficiencies found during the final occupancy inspection shall result in additional fees billed to the Contractor for re-inspection at a rate of \$65.00 per hour, per Inspector, portal to portal, plus expenses. With this in mind, the contractor should have completed his own systems testing and inspection punch list and made the corrections necessary in order to eliminate re-inspections as much as possible. When members of state departments or other interested parties request a construction site inspection it will be essential to complete the enclosed **“Request for Building Site Inspection”** form and fax or mail it to the Division of State Fire Marshal for logging in and routing to the appropriate field office. The local field inspector will then contact the requestor to make final arrangements for the inspection.

This request form has to be completed in its entirety, otherwise, the request for inspection will not be granted. Additionally, if the plans are found to still be disapproved or rejected by this office, the inspection will not be performed and a stop work order will be issued until the plans are submitted, approved, and the plans review fee is paid in full. Should you have any questions, please notify the Plans Review Section (850) 922-3171 prior to mailing this request form.

Should the project not pass inspection due to various deficiencies, a re-inspection within 30 days should be scheduled with the Inspector at that time. If the corrections cannot be made within that required time frame, it is the responsibility of the agency or requesting party to complete the attached **“Request for Building Site Inspection”** form and submit it to the State Fire Marshal's Office in Tallahassee, noting the date in which the project will be ready for re-inspection in order for him to reschedule the site for a re-inspection.

FIRE ALARM
SUBMITTAL REQUIREMENTS

1. Contractor's name, address, phone and license number.
2. Job site address, occupancy type, design criteria (which NFPA standard, local ordinance, state code the system is designed to meet).
3. General description of how the system will operate. What will activate the system; will it go into general alarm or ring by zone; will it annunciate; will it be monitored by a central station; will the air handling system be shut down, etc.
4. Itemized list of equipment to be used showing quantity, manufacturer, model number, type of device, and CFM number.
5. Standard battery calculations showing enough standby time to meet either 24 or 60 hours standby time.
6. Voltage drop calculations showing that voltage drop does not exceed 5% drop.
7. Cut sheets for each device being installed and listed in Item #4 above.
8. Drawing showing location of devices, wire runs, number of conductors, zones, end-of-line resistors, and typical wiring method used on the devices.

DIVISION OF STATE FIRE MARSHAL

BUREAU OF FIRE PREVENTIION

PLANS REVIEW SECTION

PAYMENT INFORMATION

The attached check is for the review of plans that have been submitted to the Division of State Fire Marshal for **Leased buildings**.

- Project Name: _____
 - Building Construction Cost _____
 - Amount of Check (or Transfer) _____
 - Date: _____
-

For Accounting Purposes Only:

For journal transfers, our Samas Number is:

46-10-2-39300146010000-00-000100-00

Benefiting Object Code #00100

(Please submit a copy of the journal transfer form with plans)

Your agency will then be billed for bookkeeping purposes

BILLING TYPE	TYPE	CLASS	FEE TYPE	AMOUNT
F	14	10	F	\$

Please Make Checks Payable To:

Department of Insurance

(See page one of this booklet for sending instructions)

Submitter

**STATE FIRE MARSHAL
REQUEST FOR BUILDING SITE INSPECTION**

I. GENERAL INFORMATION (Print or Type)

REQUESTOR'S NAME: _____

OFFICIAL TITLE: _____

STATE AGENCY: _____

II. TYPE OF INSPECTION: (CIRCLE APPROPRIATE ONE)

FINAL INTERMEDIATE SPRINKLER SYSTEM (ABOVE or BELOW GROUND)

ALARM SYSTEM HOOD SYSTEM PRE-OCCUPANCY

OTHER (SPECIFY):

NAME, STREET ADDRESS OR EXACT LOCATION OF FACILITY:

III. INSPECTION DATE: _____

(Provide this office with a MINIMUM of ten (10) days to two (2) weeks notice prior to requested date of inspection)

IV. STATE FIRE MARSHAL'S FILE #: _____

(Without this file #, your request will not be granted. Contact this office should you need assistance)

V. OCCUPANCY CLASSIFICATION: _____

(BUSINESS, ASSEMBLY, ETC.)

VI. SQUARE FOOTAGE & HEIGHT OF BUILDING: _____

VII. SPECIAL INFORMATION:

LIST THE FACILITY'S LIFE SAFETY FEATURES:

(Sprinkler, Standpipe, Fire Alarm, Smoke Control, other)

VIII. TYPE OF BLDG. CONSTRUCTION: _____

IX. SIGNATURE LINE _____

NAME: _____

PHONE NUMBER: _____

FAX ALL REQUESTS TO

MARK HEALEY

Bureau of Fire Prevention – Plans Review Section
200 East Gaines Street (or) hand-deliver to 325 John Knox Road
Tallahassee, Florida 32399-0342
(850)922-3171 * FAX – (850)922-2553

ARCHITECT/ENGINEER'S ESTIMATE SUMMARY & BUDGET COMPARISON

STATE UNIVERSITY SYSTEM OF FLORIDA

Project Name: _____

BT: _____

Date: _____

Estimated Building Construction Cost						Submittal Phases of Probable Construction Cost (\$)					
Space Type	NASF	NASF/GSF Factor	(a) GSF	(b) Const. Cost per GSF (major space type cost/GSF or sample bldg. Average cost/GSF)	Total cost (Building Const. Cost) (axb)	Approved Program NASF Date:	Con. Scheme NASF Date:	Adv. Scheme NASF Date:	Des. Dev. NASF Date:	50% CD NASF Date:	100% CD NASF Date:
Classroom											
Teaching Laboratory											
Research Laboratory											
Study											
Instructional Media											
Auditorium/Exhibition											
Gymnasium											
Student Academic Support											
Office/Computer											
Campus Support											
Space Total											
Proposed Additive Alternates (@Design Development Submittal with Estimated Dollar Value)					Efficiency Factor*						
					Total Gross Square Footage						
					Cost per GSF						
					Building Construction Cost (GSF x Cost per GSF)						
1 _____											
2 _____											
3 _____											
4 _____											
5 _____											

Professional Services Guide Criteria (per subparagraph 3.14.2):
 Building Gross Sq.Ft. (3.14.2.1)
 Net Assignable Sq.Ft. (3.14.2.2)
 Covered Walkway GSF (3.14.2.3)

* Insert Predominant Space Type Factor Used for Calculating Overall GSF

ARCHITECT/ENGINEER'S ESTIMATE SUMMARY & BUDGET COMPARISON

STATE UNIVERSITY SYSTEM OF FLORIDA

Project Name: _____

BT: _____ Date: _____

Submittal Phases of Probable Construction Cost (\$)						
1. Construction Components	Approved Program	Con. Scheme	Adv. Scheme	Des. Dev.	50% CD	100% CD
	Date:	Date:	Date:	Date:	Date:	Date:
a) Building Construction Cost						
b) Environmental Impacts/Mitigation						
c) Site Preparation/Demolition						
d) Landscape/Irrigation						
e) Plazas/Walks/Bikepaths						
f) Roadway Improvements						
g) Parking (Number of Spaces)						
h) Telecommunications (interior/exterior)						
i) Electrical Services						
j) Water Distribution System						
k) Sanitary Sewer System						
l) Storm Water System						
m) Chilled Water System						
n) Energy Efficient Equipment						
Subtotal Estimated Construction Components						

ARCHITECT/ENGINEER'S ESTIMATE SUMMARY & BUDGET COMPARISON

STATE UNIVERSITY SYSTEM OF FLORIDA

Project Name: _____ BT: _____ Date: _____

Submittal Phases of Probable Construction Cost (\$)	
2. Other Project Components (per approved program \$)	
a) Land/Existing Facility Acquisition	
b) Professional Fees	
Base Agreement (%)	
Special Consultants (list type)	
Construction Manager (approx. 1%)	
c) Fire Marshal (.0025)	
d) Inspection Services	
Project Representative	
Roof Inspector	
Threshold Inspector	
e) Insurance Consultant (.0006)	
f) Surveys/Tests	
Topographical Survey	
Geotechnical Tests	
Construction Test (Concrete, HVAC, etc)	
g) Permit/Impact/Environmental Fees	
Permits	
Impact	
Environmental	
h) Art Work (.005)	
i) Furnishing & Equipment	
j) Contingencies	
Subtotal Other Project Components	
Total Project Cost (Items #1 & #2)	

COST CONTAINMENT GUIDELINES

Exceptions to the State University System Cost Containment Guidelines, which were not included and approved on a previous submittal, are being recommended:

Yes No

*If "Yes", attach the relevant sheet(s) from the Cost Containment Guidelines with the comments and justifications noted

Signature

Date

FACILITY CLASSIFICATION FOR ENERGY CONSUMPTION

University/Campus: _____
 Project Name: _____
 Building Name: _____
 Additional Area: _____ GSF, on line for PO&M funding during _____ of _____
 (Month) (Year)
 Renovated Area: _____ GSF, on line for PO&M funding during _____ of _____
 (Month) (Year)

Total Energy Factor Calculation:

Criteria		Factors
A.	Is 70% or more of the GSF of this facility air conditioned? Yes = 1 No = 0	A=
B.	Is the facility being designed or renovated after 1989? Yes = 10 No = 1	B=
C.	% of the Gross square footage used for Labs or Research: _____% Multiply % times 20	C=
D.	% of outside air supplied to the facility: _____% Multiply % times 40	D=
E.	Does the facility have a heavy equipment load? Yes = 15 No = 1 <i>(Computer equipment, research, equipment, autoclaves, fume hoods, etc.)</i>	E=
F.	Is this facility an agricultural or maintenance utility shed? Yes = .5 No = 1	F=

FORMULA	CALCULATION	RESULT
$TEF \text{ Calculation} = \left[1 + A * \left[\frac{B + C + D + E}{100} \right] \right] * F$	$TEF \text{ Calculation} = \left[1 + _ * \left[\frac{_ + _ + _}{100} \right] \right] * _$	TEF = _____

Facility Classification:

(Check applicable facility class based on Total Energy Factor _____)

TEF = 1.00	Facility Class A - Low Energy Usage Building <i>A building with less than 70% of the gross square footage receiving conditioned air.</i>
TEF = 1.01 to 1.25	Facility Class B - General Office Building <i>A building that typically contains classrooms, offices, and administrative space.</i>
TEF = 1.26 to 1.29	Facility Class C - General Classroom Building <i>A building that typically contains classrooms, offices, administrative and special spaces such as general teaching labs, auditoriums, etc.</i>
TEF = 1.30 to 1.49	Facility Class D - Fine Arts, Specialized Use, Student Activities Building <i>A building that typically contains classrooms, offices, auditoriums, general patient care and special support space such as locker rooms, teaching gyms, exercise rooms, studios.</i>
TEF = 1.5- to 1.60	Facility Class E - General Science Building <i>A building that typically contains classrooms, offices, wet and dry instructional labs to support general instruction and research.</i>
TEF = 1.61 TO 1.85	Facility Class F - Research, Medical, Advanced Technology Building <i>A building that typically contains classrooms, offices, and highly specialized labs supporting upper level undergraduate programs, graduate programs, medical technology and sponsored research efforts</i>
TEF = < 1.00	Facility Class G - Agricultural and maintenance support sheds or buildings. <i>A building that may typically be used for agricultural and maintenance support and contains no air conditioned space and little or no utility usage.</i>

I certify that the above information is correct and accurate:

 Architect/Engineer of Record for Project (Typed or Printed Name)

 (signature)

TITLE BLOCK INFORMATION

CONTENT: The following information shall be provided in the title block of each drawing:

Name of University
Project location
State Project Number
State University System of Florida

Sheet Title/Name
Phase of development
*(i.e. Conceptual Schematics, Advanced Schematics, Design Development, 50%,
100% Construction Documents)*

Name of Architect/Engineer
Address of Architect/Engineer
Telephone number of Architect/Engineer

Sheet Number
Date of preparation
Initials of preparer
Signature of reviewer
Date of review

(On each sheet, as applicable)
Name of Consultant
Address of Consultant
Telephone number of Consultant

ORGANIZATION: The basic organization of the title block shall be the same for each drawing, changing the information on each sheet as appropriate.

The sheet number shall always appear either on the lower right hand corner or along the right margin of the drawing.

SEAL AND SIGNATURE: Each drawing shall be signed, sealed and dated by the responsible professional.

TITLE SHEETS, PAGES AND BINDINGS

The title block for drawing should be made as simple as possible, and should contain the following information

Project Title
Project Location
University Name
State Project Number

Name, Address and Telephone Number of Architect/Engineer

As appropriate
Name, Address and Telephone Number of Consultant

The cover of the Project Manual may be of any style or format, as long as it is consistent with the above outline. The title page may be omitted if the cover provides the prescribed content.

The title sheet for the drawing may serve as the drawing cover or a plain sheet may be used for protection.

Project Manual and drawings shall be bound in such a manner as to discourage separation or removal of pages.

ENERGY LIFE CYCLE COST ANALYSIS SUMMARY FORM

STATE UNIVERSITY SYSTEM OF FLORIDA

Project Number: BT-
 Project Name and Location: _____
 Project Architect: _____
 Project Mechanical Engineer: _____
 Scheme Descriptions: _____
 Computer Program Used: _____

SCHEME A:
 SCHEME B:
 SCHEME C:
 SCHEME D:

BUILDING PARAMETERS:

Thermal transmittance of exterior walls, U = _____ Btuh/sq.ft.-F
 Thermal transmittance of roof, U = _____ Btuh/sq.ft.-F
 Thermal transmittance of glazing, U = _____ Btuh/sq.ft.-F
 Glazing shade coefficient SC = _____
 Building Area (Gross) A = _____ Sq.Ft.

ENERGY DATA (Mbtu/sq.ft. - year) (Mbtu = Thousands or BTUs)				
<i>ITEM</i>	<i>SCHEME A</i>	<i>SCHEME B</i>	<i>SCHEME C</i>	<i>SCHEME D</i>
Interior Lights				
Heating Primary				
Cooling Primary				
Terminal Systems				
Other Uses*				
TOTAL				

*List Other Uses: e.g. Hot water Heating, Exhaust Fans, Elevators, Exterior Lights

LIFE CYCLE COST ITEM	COST VALUE (PRESENT VALUE DOLLARS)			
<i>ITEM</i>	<i>SCHEME A</i>	<i>SCHEME B</i>	<i>SCHEME C</i>	<i>SCHEME D</i>
Initial Cost				
Replacement Costs				
Energy Costs				
O&M Costs				
Total for 25 Years				
Energy Costs/Year				

Prepared by: _____
 Date: _____
 Phone: _____

SUBMITTAL & REVIEW CHECKLIST

STATE UNIVERSITY SYSTEM OF FLORIDA

Project Number: BT-_____ Date: _____
 Project Name and Location: _____ Telephone: _____
 A/E Name: _____
 A/E Address: _____

INFORMATION SUBMITTED FOR _____ PHASE _____

	Required		A/E Sub- mission Date	Univ Action/ Approval Date	Comments
	Yes	No			
(1) PROGRAM CONFORMANCE					
(a) Comparative Area Analysis					
(b) Comparative Cost Analysis					
(2) MASTER PLAN CONFORMANCE					
(3) HIST. PRES. & ARCH. APPROVAL					
(4) SPACE ANALYSIS					
(a) Gross					
(b) Net					
(5) SITE CRITERIA					
(a) Legal Description					
(b) Boundary Survey					
(c) Topographical Survey					
(d) Geotechnical Services					
(e) Zoning Compatibility					
(f) Access & Egress Prov.					
(g) Tree Survey					
(6) SITE UTILITY AVAILABLE & PROVIDED					
(a) Electric					
(b) Water					
(c) Sewer					
(d) Gas					
(e) Storm					
(f) Telephone					
(g) Other					
(7) SITE PREPARATION					
(a) Clearing					
(b) Exist Util. (Re)moved					
(8) SITE DRAWINGS					
(9) LANDSCAPE DRAWINGS					
(10) ARCHITECTURAL DWGS & DESIGN CRITERIA					
(11) STRUCTURAL DWGS & DESIGN CRITERIA					
(12) MECHANICAL DWGS & DESIGN CRITERIA					
(13) PLUMBING DWGS & DESIGN CRITERIA					
(14) ELECTRICAL DWGS & DESIGN CRITERIA					
(15) TECHNICAL SPECIFICATIONS					
(16) NON-TECH. SPECIFICATIONS					
(17) BID PROCEDURE					
(a) Base Bid					
(b) Alternates (Additive)					
(c) Special/Supplementary General Conditions					
(18) LIFE CYCLE ANALYSIS					
(19) COST ESTIMATE & CERTIFICATION INCLUDING ALTERNATES					
(20) AVAILABLE FUNDING VS. ESTIMATES					
(21) CODE COMPLIANCE					
(a) Standard Building Code(s)					
(b) NFPA Life/Safety Code					
(c) Disabled Requirements					
(d) Code Summary on Drawings					
(e) SREF Space Standard					
(f) Other					

SUBMITTAL & REVIEW CHECKLIST (Cont'd)

Project Number: BT-_____

Project Name and Location: _____

INFORMATION SUBMITTED FOR _____

PHASE _____

	Required		A/E Sub- mission Date	Univ Action/ Approval Date	Comments
	Yes	No			
	(22) REGULATIONS				
(a) Grant					
(b) Asbestos					
(c) Department of Env. Protection					
(d) Other					
(23) PERMITS					
(a) Local Building					
(b) US Army Corps of Engineers					
(c) Dredge & Fill					
(d) Electrical					
(e) Plumbing					
(f) Sanitary					
(g) Environmental					
(h) Department of Env. Protection					
(i) Water Management					
(g) Other					
(24) REVIEWS & APPROVALS					
(a) Hotel and Restaurants (DBPR)					
(b) County Health Unit					
(c) Pollution Control (DEP)					
(d) Department of Env. Protection					
(e) Elevator (DBPR)					
(f) Asbestos (DLES)					
(i) Water Management					
(g) Other					
(25) OTHER PROJECT REQUIREMENTS					
(a)					
(b)					
(c)					

FLORIDA INTERNATIONAL UNIVERSITY **BID TABULATION FORM**

Project Name:
 Project Number:
 Construction Budget:

Bid Opening Time:
 Bid Opening Date:
 Bid Opening Location:

BID TABULATION BIDDERS	Bid Bonds	Addenda Rec'd	Subs Listed	MBE %	BASE BID	ALTERNATES			REMARKS	
						ALT #1	ALT #2	ALT #3		

Scope of Alternates: (All Alternates must have a typed explanation)
 Alternate #1:
 Alternate #2:
 Alternate #3:

Bids Opened By:
 Bids Tabulated By:
 Bids Witnessed By:

Date:
 Date:
 Date:

CONSTRUCTION CONTRACT
FACT SHEET

PROJECT NAME: _____

PROJECT NUMBER: BT _____

PROJECT LOCATION: _____

Full Name & Address of Contractor: _____

Contractor's Federal I.D. No.: _____

Full Legal Name & Address of A/E: _____

CONTRACT INFORMATION *(If the project has multiple phases with separately identified completion and liquidated damage provisions times, list information for each phase individually.)*

1. Times of Commencement and Completion:

Substantial Completion	_____	Calendar Days
Final Completion	_____	Calendar Days, after Substantial Completion

2. Liquidated Damages: \$ _____

3. Contract Sum: \$ _____

Including Base Bid and Additive Alternates _____ thru _____ *(if alternates are not included, insert "N/A").*

4. The Contract Documents:

a. Drawings

Drawings Title: _____

Drawings Date: _____

(Attach a list of individual drawings sheets.)

b. Specifications

Specifications Title: _____

Specifications Date: _____

Consisting of sections listed in the *(list indexes and/or tables of contents.)*

c. Addenda

Addendum No. _____ dated _____ consisting of _____ *(number of pages and/or sheets)*
Addendum No. _____ dated _____ consisting of _____ *(number of pages and/or sheets)*

5. Form of Agreement: if any language in the standard Owner-Contractor Agreement was revised in the Project Manual, attach a highlighted copy of the revised portion(s).

STANDARD INVOICE FORM

ARCHITECT/ENGINEER INVOICE

To: FLORIDA INTERNATIONAL UNIVERSITY
 Facilities Construction
 11555 SW 17 St.
 Miami, FL 33199

Invoice Number: _____
Page: 1 of 1 Pages
Date: _____
Federal ID: _____
Project Number: BT
Project Name: Project Name

From: _____

SERVICE	TOTAL FEE	% Comp.	AMOUNT DUE	LESS PREVIOUSLY BILLED	AMOUNT DUE THIS INVOICE
Pre-Design (PD)					
Concept Schematic Design (CSD)					
Advanced Schematic Design (ASD)					
Design Development (DD)					
% Construction Documents (% CD)					
% Construction Documents (GMP CD)					
% Construction Documents (% CD)					
100% Construction Documents (100% CD)					
Corrected/Conformance Documents					
Bidding or Negotiation Phase					
Construction Administration (CA)					
Substantial Completion					
Final Completion					
Post Occupancy Inspection & Report					
Auth #1 (Survey)					
Auth #2 (Geotech.)					
Auth #3 (Life Cycle Analysis)					
Auth #4 (Project Rep.)					
Auth #5 (Addn to drawings-CO)					
Auth #6 (Materials testing)					
GRAND TOTALS	\$ -		\$ -	\$ -	\$ -
			Total due Architect/Engineer		\$ -
			* Amount payable directly to:		\$ -
			* Amount payable directly to:		\$ -

CERTIFIED TRUE AND CORRECT BY:

SUPPORTING DOCUMENTS FOR A/E INVOICES (A/E Initial):

 Signature & Typed Name of Principal

- Activation Letter of phase being invoiced _____
- Verify current Design Status Report _____
- Verify current Construction Status Report _____
- Approved Contractor Pay Certification _____
- Additional Service Authorizations _____

UNIVERSITY APPROVAL	Date	Signature
Date Received (FC Project Manager):	_____	_____
Services Rendered as Invoiced (FC Project Manager):	_____	_____
Invoice Consistent with Contract:	_____	_____
Invoice Approved (FC Director):	_____	_____

INVOICING INSTRUCTIONS:
 Please prepare invoices properly to avoid delaying payment. For complete instructions, consult the Professional Services Guide. Invoice using this standard form, and number consecutively starting with "1." Submit signed original (attach appropriate back-up documents to the invoices). Consultant's invoice(s) should be marked "Approved" and signed on the face by a principal of the A/E firm. If payment is to be made directly to the consultant, indicate above with an asterisk beside the amount due the consultant.

 * University Project Manager verifies receipt of required reports:

INVOICE

ARCHITECT/ENGINEER INVOICE

To: FLORIDA INTERNATIONAL UNIVERSITY
 Facilities Construction
 11555 SW 17 St.
 Miami, FL 33199

Invoice Number: 7

From: RA Architects
 500 Main Street
 Wesland, FL 33333

Page: 1 of 1 Pages
Date: May 6, 2008
Federal ID: 59-1234567
Project Number: BT-000
Project Name: CLASSROOM BUILDING

SERVICE	TOTAL FEE	% COMP.	AMOUNT DUE	LESS PREVIOUSLY BILLED	AMOUNT DUE THIS INVOICE
Program Verification	\$ 30,815.00	100%	\$ 30,815.00	\$ 30,815.00	
Conceptual Schematics	\$ 30,815.00	100%	\$ 30,815.00	\$ 30,815.00	
Advanced Schematics	\$ 46,223.00	100%	\$ 46,223.00	\$ 46,223.00	
Design Development	\$ 46,223.00	100%	\$ 46,223.00	\$ 46,223.00	
25% Construction Documents	\$ 61,631.00	100%	\$ 61,631.00	\$ 61,631.00	
50% Construction Documents	\$ 15,708.00	100%	\$ 15,708.00	\$ 15,708.00	
75% Construction Documents	\$ 77,038.00	14%	\$ 10,785.32	\$ 4,700.00	\$ 6,085.32
100% Construction Documents					
Construction Administration	\$ 4,500.00	100%	\$ 4,500.00	\$ 4,500.00	
AUTH-01 (describe service)	\$ 4,200.00	100%	\$ 4,200.00	\$ 4,200.00	
AUTH-02 (describe service)	\$ 9,800.00	100%	\$ 9,800.00	\$ 9,800.00	
AUTH-03 (describe service)	\$ 2,500.00	100%	\$ 2,500.00	\$ 2,500.00	
AUTH-04 (describe service)	\$ 90,000.00	9%	\$ 8,100.00		\$ 8,100.00
AUTH-05 (describe service)	\$ 14,020.00	0%			
AUTH-06 (describe service)	\$ 8,000.00	42%	\$ 3,360.00	\$ 2,100.00	\$ 1,260.00
GRAND TOTALS	\$ 441,473.00		\$ 274,660.32	\$ 259,215.00	\$ 15,445.32
			Total due Architect/Engineer		\$ 14,185.00
			* Amount payable directly to:		\$ 1,260.00
			* Amount payable directly to:		*

CERTIFIED TRUE AND CORRECT BY:

R. Anderson

R. Anderson, President

Signature & Typed Name of Principal

SUPPORTING DOCUMENTS FOR A/E INVOICES (A/E Initial):

Activation Letter of phase being invoiced	RA
Verify current Design Status Report	RA
Verify current Construction Status Report	RA
Approved Contractor Pay Certification	RA
Additional Service Authorizations	RA

UNIVERSITY APPROVAL	Date	Signature
Date Received (FC Project Manager):		
Services Rendered as Invoiced (FC Project Manager*):		
Invoice Consistent with Contract (FC Accountant):		
Invoice Approved (FC Director):		

INVOICING INSTRUCTIONS:
 Please prepare invoices properly to avoid delaying payment. For complete instructions, consult the Professional Services Guide. Invoice using this standard form, and number consecutively starting with "1." Submit signed original (attach appropriate back-up documents to the invoices). Consultant's invoices should be marked "Approved" and signed on the face by a principal of the A/E firm. If payment is to be made directly to the consultant, indicate above with an asterisk beside the amount due the consultant.
 * University Project Manager verifies receipt of required reports:

STATE OF FLORIDA VOUCHER FOR REIMBURSEMENT OF TRAVEL EXPENSES				Check One: <input type="checkbox"/> Officer/Employee <input type="checkbox"/> OPS <input type="checkbox"/> Nonemployee/ind. Contractor		SITE		FUND		PROGRAM	
NOTE: USE THIS FORM FOR ALL TRAVEL AFTER 07/01/2006						-		-			
TAR #	TRAVELER PANTHER ID	TRAVELER NAME	AGENCY	HEADQUARTERS	RESIDENCE (CITY)	Dept ID / Proj ID					
DATE	Travel Performed From Point of Origin To Destination	Purpose or Reason (Name of Conference)	Hour of Departure And Hour of Return	Meals for Class A & B Travel	Per Diem or Actual Lodging Expenses	Class C Meals	Map Mileage Claimed	Vicinity Mileage Claimed	Other Expenses		
									Amount	Type	
			5:00 AM ▼			Effective July 1, 2002 Class C expenses are not reimbursed					
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
			5:00 AM ▼								
Statement of Benefits to the State: (Conference or Convention)						Column Total	Column Total	Column Total	Total Miles = Paid at : 0	Column Total	Summary Total
						\$0.00	\$0.00	\$0.445	\$0.00	\$0.00	\$0.00
Revolving Fund:			Advance:			Less Advance Received					
Check No.: _____			Warrant No.: _____			Less Class C Meals (Official Employees Only)					
Check Date: _____			Statewide Doc. No.: _____			Less Non-Reimbursable items included on Purchasing Card					
Agency Voucher No.: _____			Agency Voucher No.: _____			Net Amount Due Traveler					
						Net Amount Due The State					
I hereby certify or affirm and declare that this claim for reimbursement is true and correct in every material matter, that the travel expenses were actually incurred by me as necessary in the performance of official duties; that per diem claimed has been appropriately reduced by any meals or lodging included in the convention or conference registration fees claimed by me, and that this voucher conforms in every respect with the requirements of Section 112.061, Florida Statutes.						Pursuant to Section 112.061 (3) (a), Florida Statutes, I hereby certify or affirm, that to the best of my knowledge the travel was on official business of the State of Florida and was for the purpose(s) stated above.					
Traveler's Signature: _____			TRAVELER'S TITLE			Supervisor's Signature: _____			Panther ID: _____		
Date Signed: _____						Supervisor's Title: _____					
						Signature Date: _____			Telephone # _____		
Form DBF-AA-15 (Rev. 10/06)											

DIRECT BILLED ITEMS (CARRIER, RENTAL CAR, REGISTRATION, ETC.)
THIS SECTION REQUIRED TO BE COMPLETED WHEN COMMON CARRIER/STATE VEHICLE#/REG FEES/GROUP HOTEL IS BILLED DIRECTLY TO THE UNIVERSITY

Date	Ticket Number or State Vehicle Number	From	To	Amount	Name of Common Carrier/Vendor
Total>				\$0.00	

FLORIDA INTERNATIONAL UNIVERSITY PURCHASING CARD CHARGES
THIS SECTION REQUIRED TO BE COMPLETED ONLY WHEN TRAVEL RELATED EXPENSES ARE PAID BY USING THE STATE OF FLORIDA PURCHASING CARD

Date	Merchant/Vendor (List Air Carrier and Ticket # if applicable)	Description of Item/Expense Report #/Dept-Proj ID#	Amount
Total>			\$0.00

THIS SECTION REQUIRED TO BE COMPLETED ONLY WHEN NON-REIMBURSABLE ITEMS WERE PURCHASED USING THE STATE OF FLORIDA PURCHASING CARD

Date	Merchant/Vendor	Description of Item/Expense Report #/Dept-Proj ID#	Amount
Total (This amount must appear on the line "Less Non-Reimbursable Items Included on Purchasing Card" on the first page)			\$0.00

GENERAL INSTRUCTIONS

Class A travel - Continuous travel of 24 hours or more away from official headquarters.
Class B travel - Continuous travel of less than 24 hours which involves overnight absence from official headquarters.

Breakfast - when travel begins before 6 a.m. and extends beyond 8 a.m.
Lunch - when travel begins before 12 Noon and extends beyond 2 p.m.
Dinner - when travel begins before 6 p.m. and extends beyond 8 p.m. or when travel occurs during night-time hours due to special assignment.

Note: No allowance shall be made for meals when travel is confined to the city or town of official headquarters or immediate vicinity except assignments of official business outside the traveler's regular place of employment if travel expenses are approved and such special approval is noted on the travel voucher. Rate of Per Diem and Meals shall be those prescribed by Section 112.061, Florida Statutes.

Non-reimbursable items may not be charged on the State of Florida Purchasing Card. Inadvertent non-reimbursable charges are to be deducted from the travel reimbursement claimed on the reverse side of this form on the line "Less Non-reimbursable items included on Purchasing Card: and the above "Non-Reimbursable items: section of "State of Florida Purchasing Card Charges: section above must be completed. Per diem shall be completed at one-fourth of authorized rate for each quarter or fraction thereof. Travel over a period of 24 hours or more will be calculated on the basis of 6-hour cycles, beginning at midnight; less than 24 hours travel will be calculated on the basis of 6-hour cycles, beginning at the hour of departure from official headquarters. Hour of departure and hour of return should be shown for all travel. When claiming per diem, the meal allowance columns should not be used. Claims for actual lodging at single occupancy rate plus meal allowances should be put in the "Per Diem or Actual Lodging Expenses" column and include the appropriate meal allowances in the "Meals for Class A & B Travel" column. Claims for meals allowance involving travel that did not require the traveler to be away from headquarters overnight should be included in the "Class C Meals: column. Vicinity travel must appear in the separate column. When travel is by common carrier and billed directly to the traveler, the amount and description should be included in the "Other Expenses: column. A copy of the ticket or invoice should be attached to this form. If travel is by common carrier and billed directly to the State agency, then the "Travel Performed by Common Carrier of State Vehicle: section above should be completed. If travel is by common carrier and the carrier is paid by the use of the State of Florida Purchasing Card, then the "State of Florida Purchasing Card Charges" section above should be completed. The name of the common carrier should be inserted in the "Map Mileage Claimed" column in these instances. Justification must be provided for use of a noncontract airline (or one offering equal or lesser rates than the contract airline) or rental care (or one having lower net rate) when contract carriers are available. Additionally, justification must be provided for use of a rental car larger than a Class "B" car. If travel is performed by the use of a State-owned vehicle, the word "State" should be inserted in the Map Mileage Claimed" column on the reverse side of this form, and the above section designated as "Travel Performed by Common Carrier or State Vehicle: should be completed. If lodging is paid by the use of the State of Florida Purchasing Card, the words "Purchasing Card" should be inserted in the "Per Diem or Actual Lodging Expenses" column on the reverse side of this form, and the above section designated as "State of Florida Purchasing Card Charges" should be completed. Incidental travel expenses which may be reimbursed include: (a) reasonable taxi fare; (b) ferry fares and bridge, road, and tunnel tolls; (c) storage and parking fees; (d) telephone and telegraph expenses; (e) convention or conference registration fee. If meals are included in the registration fee, per diem should be reduced accordingly. Receipts should be obtained when required. The official Department of Transportation map should be used in computing mileage from point of origin to destination whenever possible. When any State employee is stationed in any city or town for over 30 days continuous work days, such city or town shall be deemed to be his official headquarters and he shall not be allowed per diem or subsistence after the period of 30 continuous work days has elapsed, unless extended by the approval of the agency head. If travel is to a conference or convention, the "State of Benefits to the State" section must be completed or a copy of the Authorization to incur Travel Expense, Form DBF-AA-13, must be attached. Additionally, a copy of a agenda and and registration receipt must be attached. Any fraudulent claim for mileage, per diem or other travel expense is subject to prosecution as a misdemeanor.